# Feasibility Study of Semi-Automatic Pipe Handling System and Fabrication Facility

U.S. Department of Commerce Maritime Administration

in cooperation with Avondale Shipyards, Incorporated New Orleans, Louisiana


> Transportation Research Institute

maintaining the data needed, and c including suggestions for reducing	election of information is estimated to completing and reviewing the collect this burden, to Washington Headquuld be aware that notwithstanding aromb control number.	ion of information. Send comments arters Services, Directorate for Information	regarding this burden estimate mation Operations and Reports	or any other aspect of the 1215 Jefferson Davis	nis collection of information, Highway, Suite 1204, Arlington
1. REPORT DATE AUG 1978		2. REPORT TYPE <b>N/A</b>		3. DATES COVE	RED
4. TITLE AND SUBTITLE			5a. CONTRACT NUMBER		
Feasibility Study of Semi-Automatic Pipe Handling System and Fabrication Facility			5b. GRANT NUMBER		
			5c. PROGRAM ELEMENT NUMBER		
6. AUTHOR(S)				5d. PROJECT NU	JMBER
			5e. TASK NUMBER		
				5f. WORK UNIT NUMBER	
Naval Surface War	ZATION NAME(S) AND AE rfare Center CD Co n 138 9500 MacArtl	de 2230- Design Into		8. PERFORMING REPORT NUMB	G ORGANIZATION ER
9. SPONSORING/MONITO	ONSORING/MONITORING AGENCY NAME(S) AND ADDRESS(ES)  10. SPONSOR/MONITOR'S AC		ONITOR'S ACRONYM(S)		
			11. SPONSOR/MONITOR'S REPORT NUMBER(S)		
12. DISTRIBUTION/AVAIL Approved for publ	LABILITY STATEMENT ic release, distributi	on unlimited			
13. SUPPLEMENTARY NO	OTES				
14. ABSTRACT					
15. SUBJECT TERMS					
16. SECURITY CLASSIFIC	CATION OF:			19a. NAME OF RESPONSIBLE PERSON	
a. REPORT unclassified	b. ABSTRACT <b>unclassified</b>	c. THIS PAGE unclassified	SAR	96	RESTONSIBLE FERSON

**Report Documentation Page** 

Form Approved OMB No. 0704-0188

**Executive Summary** 



Automation of the pipe fabrication process for the shipbuilding industry.

### **Executive Summary**

The primary objective of this study is to design a cost effective and semi-automatic method of fabricating pipe which will reduce the labor, material handling, storage space and required fabrication area.

Such a facility for the shipbuilding industry must be designed to handle 1½ inch through 24 inch diameter pipe and all ASTM Class and MIL-SPECS, and Schedules and alloys of pipe used in shipboard systems. The facility must be versatile and equipped to handle repair jobs and specialty items, as well as new vessel piping systems.

Our technical approach to this project fulfilled the stated objectives of the National Shipbuilding Research Program as established under the Merchant Marine Act of 1970. We have determined that a functional semi-automated Pipe Shop is feasible.

The following functions represent a pipe fabrication system which can be implemented along with certified procedures where necessary, either in part or as an entire s ystem at any major shipyard.

- 1. A systematic rack storage and locator system for all types of pipe, in sizes from 11½ inch through 24 inch must be established. The storage racks must provide for loading, selecting and off-loading onto a transfer system automatically.
- 2. A sorting and automatic feed system must be installed at the pipe storage rack so that an operator can automatically select pipe from the rack, load it onto a conveying system and convey it to the work station.
- 3. The automatic conveying system, for movement of pipe from one work station to another, must be equipped with an automatic unloading device at each station, and a reserve area to hold pipe for each machine.

- 4. A measuring system must be installed to automatically measure pipe for cutting to length, locating holes and other layout requirements.
- 5. A system must be furnished to mark each component of the assembly with the specific part number as identified on the production drawings.
- 6. Cutting and end preparation machines must be provided. This function is extremely important since, in order to obtain good welding results, the use of machine cutting is an absolute necessity. At this point, all scrap must be conveyed out of the shop area by means of conveyors or other handling equipment.
- 7. An automatic flange fitting and welding device must be installed and have the capability of processing the pipe alloy mix as well as selecting the flange, orienting it properly, tacking it and welding both inside and out.
- 8. Adequate numerically controlled bending equipment must be provided capable of two diameter bending for up to Schedule 80 pipe 10 inches in diameter. Adequate bending facilities for larger pipe will depend on the number of ship systems for which larger pipe is required. It can be either hot bending or vibratory bending. An important function of this bending equipment, in addition to the two diameter bending for pipe up to 10 inch diameter, is the capability of being automatically fed and bent with flanges installed on both ends.
- 9. Various types of welding equipment must be selected which will be required to process the mix of pipe through the system. Rolling devices must be provided for the welding of straight pipe, and these should incorporate automatic loading and unloading mechanisms as well. The development of semi-automatic welding devices for sub-assembly areas is desirable, along with certified welding procedures.

- 10. Assembly areas must be equipped with manipulator fixtures designed so that assembly of pipe sections can be processed in an effective manner. Manipulators are to be fitted with semi-automatic loading and unloading devices, and must be capable of positioning the main body of pipe into position so that fitting and welding can be accomplished. The welding devices should be selected and developed concurrently with the manipulator fixtures for this function.
- 11. The configuration and quantity of X-ray booths and equipment required to support the maximum work load of this work station and provide handling equipment required for loading, manipulating and unloading the X-ray booths must be determined.
- 12. A semi-automatic internal and external blasting and coating system for pipe must be provided. A bypass would be included so that all full length pipe which does not require further processing would be channeled directly to the assembly area.
- 13. A specialty area for the fabrication of the inevitable "exception" must be designated. Machines, tools and handling equipment must be selected for processing specialty items of a configuration and volume not suitable for automatic and semi-automatic processing. This specialty area would be situated so that it would be accessible to the automatic conveying system. In general, work in this area would be accomplished by hand.
- 14. A final product storage system must be provided where the fabricated pipe and specialty items can be palletized and stored in a racking system, in usage order, until required. A locator system, to be used for accountability and retrieval, should control the storage function.
- 15. Transportation and handling equipment must be provided for selection, load-out and delivery of fabricated pipe to the installation site.
- 16. The computer software package must be developed to support this fabrication shop. Our investigation has revealed that all man-hour savings to be experienced by an automated system can be completely offset by a major increase in the engineering staff necessary to provide the drawing and other data in a timely manner. Therefore, a computer software package must be developed to operate this system and have the capability of preparing pipe detail drawings. As these drawings are being prepared, the program should select required information from data banks which would allow the concurrent preparations of bills of material, shop production schedules, material flow schedules, cutting lists, assembly marking and bending data, machine loading schedules and final disposition and delivery schedules.

The use of a mini-computer, supported by a primary computer, which could utilize a digitizer or some other method to design, update and revise the various parts of the system is envisioned.

The software package must be in the form best suited to the specific facility and working methods of the particular system, such as the order card of numerically controlled equipment, tape for tape controlled equipment and numerical list for other equipment and manual operation.

The cost to implement. a system as described would require a capital investment of two to five million dollars dependent upon the existing shop facilities and the size, type and volume of the pipe to be processed.

With an investment of this magnitude, management can expect at least two things: (1) a return on their investment of approximately 35.4 percent per year depending on the facility; and (2) an extremely efficient pipe fabrication shop capable of meeting required production schedules. The system contemplated is designed to produce 150 pipe spools per day, with corresponding limited reduction of skiIled shop manpower.

Fabrication cost of ship piping systems is roughly equal to one fourth of the total hull cost of a ship. For a 176,000 DWT tanker, this amounts to approximately 200,000 manhours. The study revealed that through automation a percentage of the required manhours can be reduced in the following functions: Handling 68 percent; Fitting 55 percent; Welding 35 percent; Cleaning 79 percent and Coating 86 percent. These percentages are based on LASH vessel construction since all basic data is applicable to this series of ships. An overall percentage reduction in fabrication manhours equates to approximately 39.8 percent per shipset.

## Foreword

#### **Foreword**

Approximately two years ago, Avondale Shipyards, Incorporated submitted a proposal to the United States Maritime Administration covering the development of a semi-automatic pipe fabricating facility. This proposal was accepted and, since that time, we have been conducting an in-depth study of the subject. This study has been conducted at Avondale Shipyards' main Pipe Shop, and utilizes manual fitting, welding and burning as a data base, along with the original shop layout and flow diagram. Originally, Avondale Shipyards had a production capacity of 50 to 55 spool pieces per day with a complement of 76 people in this department and 8 people for surface preparation and coating. Basic changes which have been accomplished during this study such as wirefeed welding in lieu of stick welding, provision of a cutting station, installation of contour cutting machines and utilization of a limited amount of turning and manipulation equipment have increased our production to 60 or 65 spool pieces per day.

The following paragraphs summarize the state of the art of automated pipe fabrication systems:

There are several equipment manufacturers in the world today who have developed, and are marketing, automated pipe fabrication equipment for the shipbuilding and pipe fabrication industries.

Japan has two major manufacturers. The Ishikawajima-Harima Heavy Industries Company, Limited, or IHL system is very efficient, but is limited as to pipe diameter and to the processing of steel pipe only. It provides storing, marking, flange fitting and welding, cutting, bending, loading and transferring capabilities.

The Mitsui Engineering and Shipbuilding Company has a system called MAPS, which is similar to the IHI system in that it is limited in pipe diameters and does not provide for alloy mix suitable to the shipbuilding industry. We feel, however, that Mitsui could provide a complete shop. They have done outstanding planning in the development of a complete pipe facility as envisioned by this study.

IHI and Mitsui, as well as Hitachi Shipbuilding Company, Limited, can provide software packages to support the required degree of automated hardware and material control. Mitsui's software package is very sophisticated and seems to provide more desirable features than any of the existing systems. It has the capabilities for the engineering requirements including preparation of detail drawings, as well as shop planning.

The Maritime Administration has awarded a feasibility contract to Newport News Shipbuilding and Drydock Company for the development of a software package which would provide engineering, including digitizing, in support of an automated design system. If completed in sufficient time, Avondale Shipyards will consider integrating the Newport News system with other available software packages to form an integrated engineering/ shop control program.

In Germany, Oxytechnik has the capability of providing complete automated systems with the exception of branch welding, sub-assembly type work and a software package necessary for engineering and control of equipment. This manufacturer has been extremely energetic in adaptations to meet the requirements of various types of pipe fabrica-

Kockums Shipbuilding Company has developed an excellent program nicknamed "System Q" and "Steer Bear" for use with the Oxytechnik system for production scheduling, engineering and material control within their own pipe fabrication shops.

Mecaval International, in France, has developed a pipe system, but it is limited to cutting, flange welding and numerically controlled bending and conveying equipment. St. Nazzair Shipyards has developed an outstanding fitting and welding system in support of the Mecaval system.

In Sweden, the ESAB systems have been limited to flange welding machines and manipulators. However, ESAB has developed exceptional welding equipment in the past, and is presently studying the feasibility of utilizing their robot in pipe welding. Preliminary data on this equipment indicates feasibility.

The Rauma Repola Shipyard in Finland has an Oxytechnik automated pipe facility which was the most complete and updated facility seen. All of this automated equipment is push button controlled. Their facility has a 100 spool per day production capability manned with 30 people. The management of Rauma Repola Shipyards indicated a better than 30 percent saving through auto-

In the United States, some welding technology has been developed, along with manipulators and turning devices.

Many companies in the United States have been visited, and a few in Europe, who are involved in processing pipe for chemical plants, oil refineries and pipe fabricating companies. In general, all pipe production we have witnessed is as inadequate, or backward, as it is in the ship building industry. . . with some noteworthy exceptions.

It has been determined that there is not a single totally automatic, or semi-automatic, pipe fabricating system available in the world today. However, most of the machines required for such systems are available in Europe, Japan and the United States.

It must be noted that the United States Department of Commerce Maritime Administration, in cooperation with Bath Iron Works Corporation, recently released a document entitled "Advanced Pipe Technology." This project is essentially a study of the mechanics of utilizing raw materials, equipment and human resources to produce finished ship piping systems, and covered state-of-the-art methods related to Piping Designed/Engineering, Piping Fabrication and Piping Assembly/Installation. Rather than duplicate the applicable data, we recommend the advanced Pipe Technology Study as a source for the detailed state-of-the-art.

**Table of Contents** 

### TABLE OF CONTENTS

Executive Summary	Page 2
Foreword	Page 6
Section IObjectives and Research Conclusions	Page 10
A. Technical Approach Reject	Page 12
B. General Rocedures	Page 12
C. Objectives and Conclusions	Page 13
D. Anticipated Benefits	Page 18
E. On-site Facility Surveys	Page 18
Section II-Proposed Semi-automatic Pipe Fabrication Facility	Page 20
A. General	Page 23
B. Basic and Principal Features	Page 23
C. General Condition	Page 24
D. Actual/Proposed Time Comparison	Page 24
E. Equipment Requirement	Page 26
F. Plan View of Pipe Fabrication Facility	Page 27
G. Isometric Layout of Pipe Fabrication Facility	Page 28
H. Illustration of Pipe Fabrication Process	Page 29
I. Production Flow and Production Rate of Pipe Fabrication Facility	Page 30
J. Specification of Equipment and Machines with Concept Drawings	Page 31
Section III-Computer Software System	Page 55
A. Summary	Page 57
B. General	Page 57
C. GPS (Graphic Piping System)	Page 59
D. Pipe Shop Production Control System	Page 63
E. Palletizing System	Page 65
F. Computer Software Outputs	Page 66
G. Computer Configuation to Accomplish Software Package	Page 78
Section IV-Advanced Research and Development	Page 79
A. General	Page 82
B. Van-Stone Couplings	Page 82
C. Cypress Welding Research and Development	Page 82
D. ESAB Industrial Robot Welding Research and Development	Page 82
E. T/Drill Branch Collaring 90 Degree Research and Development	Page 82
F. Machine Cutting Branches	Page 82
Section V—Equipment Suppliers	Page 90
A. General	Page 92
B. Pipe Shop Equipment Suppliers	Page 92
C. Hardware System Suppliers	Page 92
D. Software Package Suppliers	Page 92
Acknowledgements	Page 94

## **Section I**

### **Section I**

Objectives and Research Conclusions Index

- A. Technical Approach ProjectB. General Procedures
- C. Objectives and Conclusions
- D. Anticipated Benefits
- E. On-site Facility Surveys




Manual contour burning process.

#### A. Technical Approach Project

The magnitude of this project made it necessary to subdivide the project into sixteen sub-projects functionally oriented. During the feasibility study, any one of the sixteen sub-projects could be developed independently of the other in respect to function, equipment, design or selection. Attention was given to sub-project interface to assure total project integration.

- 1. Technical Approach
  - a. Preliminary facility layout showing work stations, machine and equipment location, and conveying system routing was developed.
  - b. Flow process charts showing flow through the facility, detailing the process through each work station, were established.
  - c. Preliminary machine concept drawings were developed.
  - d. Preliminary purchase equipment and machine listing were established.
  - e. Existing equipment utilization listing is available.
  - f. Preliminary equipment and machine installation phasing plan is available.
  - g Interface with the Ship Producibility Program was maintained.
  - h. Semi-working scale model of the proposed facility is available.
  - Cost estimates for implementing the proposal are available.



Semi-automatic contour burning process.

- This document represents the Phase I completion report prepared and forwarded to MARAD and the Ships Production Committee for review and comments.
- k. Layout, flow charts, time studies, flow process of existing system are included and have been used to compare the existing system to the proposed system.

#### B. General Procedure

Each of the sixteen sub-projects was developed through the following standard operating procedures.

1. Determine the Present State-of-the-Art

We determined the state-of-the-art by site interviews with knowledgeable individuals in other shipyards and industries both foreign and domestic. Further, we conducted a search of literature and corresponded with selected technical societies.

2. Identify Potential Participants

Through inquiry among the various interested shipbuilders, other industries and technical society members, we developed a list of potential participants. We screened these for significant prior experiences in conducting a disciplined R & D effort oriented toward specific objectives. Further, we screened them for their potential continued interest in the shipbuilding industry.

3. Establish Priorities

The priorities for this project were based on the economic benefits of each area proposed.

4. Solicit Various Vendors, Manufacturing and Consulting Firms for Proposals

A request for proposals was issued to various vendors, manufacturers and consulting firms. The response to our inquiries has been tabulated in various groupings, and a determination was made as to those qualified to participate.

5. Evaluate Proposals

The evaluation of the proposals received was based on judging each against our previously established criteria.

Consideration was given to cost and the estimated benefits.

6. Negotiate Subcontracts

After the proposals were evaluated, we entered into definite contracts with selected sources as appropriate with prior concurrence of the contracting officer.

7. Develop and Demonstrate Prototypes

As commercially available prototypes were identified or developed, they were demonstrated under simulated and actual production conditions.

8. Evaluate Results of the Project

The data collected during research and development work was evaluated.

9. Submit Interim Reports

We submitted reports accompanied by informal oral progress reports. These were supplemented by formal progress reports.

10. Evaluate Areas for Future Study

During the progress of this project, other areas which offered potential to the shipbuilding industry are being evaluated.

11. Present Final Results and Reports

A summary of the data collected has been made and oral and written reports of the results presented.

#### C. Objectives and Conclusions

- 1. Semi-automatic Pipe Fabrication System Feasibility
  - a. Process: Determine the design of a cost effective method of fabricating pipe assemblies for shipboard systems which will reduce the labor, material handling, flow through the system and space required for storage as well as fabrication area.
  - b. Criteria The facility must be designed to handle 1¼ inch through 24 inch diameter pipe, all ASTM Classes and MIL-SPECS and Schedules, as well as copper nickle, stainless steel, etc. used in shipboard systems. The facility must be versatile and capable of handling new ship piping systems as well as repair jobs and specialty items.

The following items represent the fundamental requirements necessary for inclusion in a semi-automatic pipe fabrication system which can be installed individually or as a complete system with modification, implemented with certified procedures, where necessary, and fully utilized by any major shipyard as a production facility.

- Provide a systematic rack storage and locator system for storage of all ASTM Classes and MIL-SPECS and Schedule and copper nickel and stainless steel pipe stock.
- Provide an automatic feed pipe rack with push button select controls.
- Provide an automatic conveyance system to be used for moving pipe from one work station to another.
- Provide an automatic pipe measuring system.
- Provide an automatic marking system for part identification.
- Provide semi-automatic loaded cutting machine of a variety compatible with the alloy

mix of pipe going through the facility.

- Provide automatic flange fitting and welding devices capable of welding the alloy mix of pipe going through the facility.
- Provide semi-automatic loaded bending machines capable of producing 1½ or 2 diameter bends... and provide a hot bending device and required heat source along with this for bending extra heavy wall pipe and large diameter pipe.
- Provide the various types of welding machines to process the alloy mix of pipe going through the facility.
- Provide manipulator fixtures integrated with various types of welding machines for processing sub-sub-assemblies, sub-assemblies and assemblies.
- Provide X-ray facilities equipped with semiautomatic manipulator for positioning pipe assemblies during the time they are being processed.
- Provide semi-automatic internal and external surface preparation systems for cleaning and pipe coating assemblies.
- Provide machines, tooling and handling equipment for processing specialty items.
- Provide racking system with automatic or semi-automatic locator system for temporary storage of palletized completed pipe assemblies.
- Provide transportation and handling equip ment for transporting palletized pipe assemblies from temporary storage to the installation site.
- Provide a software package to support the fabrication facility.

#### 2. Research Conclusions

- a. Operating under the general procedure, it was determined that there is not a semi-automatic pipe fabrication facility that meets the criteria as outlined. The semi-automatic pipe fabrication systems which exist today are considered to be partial systems limited as to pipe diameter and alloy mix. The existing systems are also limited as to the processes within the systems.
- b. The existing semi-automatic pipe fabrication systems have one very important common denominator—they are very efficient, and they effect cost savings despite the limiting factors.
- c. It was determined that most of the equipment, machines and devices required to meet the cri tens are available in the world market today.

The task of modification of existing equipment, machines and devices remains, as well as the development of prototype machines that are necessary to fulfill the criteria as outlined.

#### 3. Feasibility

- a. It was determined that the criteria are sound.
- b. It was determined that the equipment, machines and devices that are available in the world market place can be purchased individually, used individually or modified and utilized by being integrated into a semi-auto-

matic pipe fabrication system.

- c. Considerable effort was directed toward studying the feasibility of machines required by the criteria but non-existent in the world today. The machines in this category have been proven feasible, however prototypes must be designed and the processes certified in order to categorize these items as production equipment.
- d. A semi-automatic pipe fabrication system as outlined in the criteria is feasible and can be installed on incremental base considering work station planning, or as a complete system, by any major shipyard. It is possible that smaller shipyards can automate on incremental base to the point that capital investments justify.

#### 4. Work Station and or Process Feasibility

The following will provide detailed information pertaining to available equipment, machines and devices and feasible equipment, machines and devices at the work station or process level.

a. Criteria-storrme of Raw Material

- Develop a systematic rack storage and locator system for storage of all pipe in sizes from 1½ inch to 24 inch diameter by wall thickness, ASTM or MIL-SPECS category, and alloy.
- Develop an automatic feed system for the pipe rack whereby an operator can select a specific pipe section from the rack, load the pipe onto the conveying system and convey the pipe section to the pre-selected work station, by-passing work stations not required. Selection, loading, conveying and work station to be push button controlled.

#### b. Research Conclusion:

Pipe storage racks meeting the criteria are available in Japan and Europe. Several foreign shipyards are presently using automatic feed racks to support their pipe fabrication facilities. Some domestic industry, such as chemical plants, oil refineries, etc. have recognized the need for systematic rack storage with automatic retrieval and have designed, fabricated and installed such racks. The storage racks seen in foreign and domestic plants varied in size, with capacities of from one week to six months' supply, with as many as 30 different sizes or alloys of pipe. The pipe racks currently installed at foreign shipyards were designed by the system supplier and made by the user. It was determined that no such racks are available for purchase as a stock item in the United States.

c. Feasibility

- Conclusions from our research prove that the storage of raw material as outlined in the criteria is feasible. Racks as described can be purchased as a production item or designed and built by the user to suit the user's needs.
- For inclusion in the proposed automatic pipe fabrication system, a prototype racking system must be designed. Conceptual drawings and specifications are included in the machine concept section of this document.

#### 5. Handling System

#### a. Criteria

It would be necessary to develop an automatic conveying system to be used for moving pipe from one work station to another. Each work station would have an automatic kick out and loading device, and would be equipped with controls to select the pieces of pipe with respect to size, wall thickness, alloy and length to be processed in sequence. Any pipe not requiring that process would by-pass the station and queue up for the next process according to the production drawing sequence.

#### b. Research Conclusions

- A conveyer of a design to transport straight pipe sections is available from domestic and foreign suppliers.
- Transporting bent or flanged pipe requires a special type of conveyer. Part of this type of conveyer can be purchased. The remainder must be designed to fit the facility.
- Loading and unloading kick outs and transfer sections are available both from domestic sources and from foreign suppliers. Some special loading and unloading devices would have to be designed to feed machines not previously automated.
- Automatic and/or push button controls are available for purchase as a stock item. The engineering requirements for proper sequencing and phasing, however, must be developed to suit the particular system being installed.
- It is possible to purchase the conveying equipment, loading and unloading kick outs and controls as a package. The user must determine, however, the type and quantity of conveyer loading and unloading, kick outs and controls required. This is a natural process during facility design and layout.

#### c. Feasibility

- Conclusions from our research prove that the handling system as outlined in the criteria is feasible.
- Part of the handling system can be purchased-the balance must be designed. Prototypes must be tested.
- Concept designs and specifications are in eluded in the machine concept section of this document.

#### 6. Measuring System

#### a. Criteria

A system must be developed which can be used to automatically measure pipe for cutting to length, bending and other layout requirements.

#### b. Research Conclusions

- The capabilities of measuring and cutting to length are available and installed on all cutting machines seen at automatic pipe fabrication facilities.
- Measuring and locating hole cuts is a manual operation in facilities visited.
- Measuring and layout of bends is automatically accomplished when using N.C. bending machines. Standard bending machine

measuring is manual.

• Assembly areas utilized manual measuring.

#### c. Feasibility

- Automatic measuring systems can be purchased for cutting machines (cut to length) and can be built into cutting machines.
- It is feasible to locate the center of holes to be cut after the pipe piece is loaded into the automatic hole cutting machine. A prototype must be designed and tested.
- Other layout requirements can be accomplished automatically. Prototype devices must be designed and tested.

## Marking (Component and Assembly Part Identification)

#### a. Criteria

Develop a system which can be employed to automatically mark each component sub-sub-assembly, sub-assembly and assembly with the specific part number called for on the production drawings. Deploy this system as an attachment to the cutting machine.

#### b. Research Conclusions

Component and assembly part identification marking is a manual operation in domestic and foreign shipyards. The method of die stamping was studied, but proved unsatisfactory. This method is not acceptable by regulatory agencies for it is a potential pipe failure point.

c. Feasibility

A prototype marking device must be designed and tested. Concept design and specifications are included in the machine concept section of this document.

#### 8. Cutting and Edge Preparation

#### a. Criteria

- Select the various cutting processes economically required to process the alloy mix of pipe going through the system. The quantity of each type of cutting machine must be controlled by the diameter range and alloy range of the specific cutting machine. Particular attention should be given to cutting speeds and quality.
- Develop an automatic loading and unloading device for each cutting machine that is push button controlled. The usable piece of pipe will be conveyed to the next work station. The scrap will automatically be dispensed for removal.
- Design edge preparation into the cutting machine for end cuts, with the exception of plasma cutting. The bevel can be done during cutting; however, provisions must be developed for final edge preparation.
- Develop an edge preparation system for hole cuts.

#### b. Research Conclusions

• It was determined that the cutting process is the most critical process in the automated systems. The point at which the pipe is cut is usually a fit and weld joint done later on during the production process. Based on this

conclusion, it became necessary to break down the criteria into types of cuts and study processes for each type. This was accomplished and the research conclusions follow.

• For square cut 1½ inch to 20 inch diameter pipe, it is essential that square cuts be processed as a machine cut utilizing a saw or cutting tool. If a bevel is required, this must be accomplished by a machine tool device. Cutting saws are available through a domestic supplier. Beveling machines are also available as a production item. Machine tool cutting and automatic beveling are available as a production item, but this type of machine is a slow process and not recommended for high volume usage. Saws are recommended for high volume pipe cutting for pipe 1½ inch to 20 inches in diameter. Pipe over 20 inches in diameter should be plasma/gas cut due to the sizing of saw (disc) blades and economics.

#### • Contour End Cuts

Plasma/gas contour cutting machines are readily available through domestic or foreign suppliers. These contour cutting machines have the capability of cutting the desired contour and beveling simultaneously. Edge preparation is necessary and presently is accomplished manually.

#### Hole Cuts

Boring machine cutting of holes is possible but not cost effective. The most cost effective production process is plasma/gas cutting, with hole edge preparation again accomplished manually. Some noteworthy develop ment work is taking place in this area. There is a system manufactured by T/Drill which can produce the holes necessary for branch pipe work. Details on this device are covered in the Advanced Study section of this document.

#### c. Feasibility

- High speed cutting saws, plasma/gas contouring machines and plasm/gas hole cutting machines are available for purchase through domestic or foreign suppliers.
- Automatic beveling machines are available.
   A prototype machine, however, must be designed and tested to meet the criteria cost effectively.
- Concept design and specifications for cutting stations are included in the machine concept section of this document for inclusion in the proposed semi-automatic pipe fabrication system.

#### 9. Automatic Flange Fitting and Welding

#### a. Criteria

Develop automatic flange fitting and welding device. Select and incorporate into the device the various welding processes required to process the alloy mix of pipe going through the system. The quantity of auto flange fitting and welding devices will depend upon the diameter range designed into the devices. Each device will have push button selectivity for

weld procedure, loading and unloading.

#### b. Research Conclusions

Automatic flange fitting and welding machines are available from foreign suppliers only. The existing machines are limited to pipe size and alloy.

 The general opinion of domestic shipbuilders is that flanging is a small part of the work load. It was determined that, through automation, this segment of the work load would expand, reducing field fitting and welding.

• During the research in this area, it was determined that if a flange finish device is desired, such a device is available from foreign suppliers. Its use would be to clean the inside weld, dressing the weldment, and that it should be included with the work station.

#### c. Feasibility

- Conclusions from our research prove that automatic flange fitting and welding is feasible. The basic machine is available. A prototype machine fitted with an interchangeable welding system must be developed.
- A prototype flange fitting device must be designed to allow for the various types of flanges used in domestic shipyards.
- An automatic loading and unloading device must be modified to fit the feed conveyer and automatic flanging machine.
- The automatic flange finishing machine must be modified and fitted with loading and unloading mechanisms.
- Concept drawings and specifications are available in the machine concept section of this document.

#### 10. Bending

#### a. Criteria

- Select and/or develop bending machines capable of producing 1½ and two diameter bends with or without flange.
- Develop automatic loading and unloading devic-one for each bending machine.
- Select bending equipment for large diameter pipe.

#### b. Research Conclusions

- Flanges on N.C. bending machines for pipe range from 2 inch to 12 inch diameter are available from foreign suppliers. The domestic bending machine manufacturers indicated no interest in developing the capability of handling flanges on bending machines over 8 inch diameter.
- Loading and unloading devices for bending machines are available from foreign suppliers.
- The volume of large pipe requiring bending may not be sufficient for automation, however vibrator bending or high frequency bending machines are available from foreign suppliers.

#### c. Feasibility

 Bending machines meeting the criteria for pipe ranging from 2 inch to 12 inch diameter are feasible.

- Loading and unloading devices are available—however, prototypes must be designed for automation and conservation of space.
- Large pipe, as outlined in the proposed Pipe Shop layout, is a low volume work loadtherefore, hot bending will suffice.
- Conceptual drawings are available in the machine concept section" of this document.

#### 11. Welding

#### a. Criteria

Select the various types of welding machines required to process the alloy mix of pipe going through the system. Develop a rolling device for welding straight pipe, incorporating an automatic loading and unloading mechanism controlled by push button.

#### b. Research Conclusions

- Various types of welding machines are available from foreign and domestic suppliers.
   Substantial research in welding technology has taken place in Europe, Japan and the United States.
- It was necessary to detail the criteria during the progress of this study. The criteria were revised to automate welding through the use of manipulating the welding gun and/or manipulating the work piece.
- Butt welds can be accomplished successfully by rolling the work piece. The welding gun is fixed in this operation.
- Branch welding 90 degrees can be accomplished by manipulating the welding gun; the work piece is fixed.
- Branch welding 45 degrees, 60 degrees can be accomplished by manipulating the welding gun and the work piece.

#### c. Feasibility

- Semi-automatic welding of butt welds and branches 90 degree, 60 degree. 45 degree is feasible through manipulating the welding gun and/or the work piece.
- Additional information on this process is available in the Advanced Study section of this document.
- Conceptual design and specifications are available in the machine concept section of this document.
- Prototype machines must be designed and tested.

#### 12. Assembly Area

#### a. Criteria

. Develop manipulators and fixtures whereby sub-sub-assemblies, sub-assemblies and assemblies of pipe sections can be processed in the most cost effective way. The manipulator is to be fitted with semi-automatic loading and unloading devices, and of a design capable of positioning the main body pipe section so that fitting and welding of tee sections can be accomplished.

#### b. Research Conclusions

• The manipulators and fixtures outlined in the criteria were studied concurrently with the welding machines.

- Work piece manipulator rolling devices and fixtures are available from domestic and foreign suppliers. However, these devices must be fitted with loading and unloading mechanisms.
- It must be noted that not one facility visited during the course of this study has made any effort to automate the assembly area.

#### c. Feasibility

- In the area of branch welding, research shows feasibility with respect to manipulating main pipe for fitting and welding 45 degree, 60 degree branches.
- Ž After prototype welding equipment is designed and tested for 90 degree branch welding, 45 degree and 60 degree prototypes will follow.

#### 13. X-ray Equipment

#### a. Čriteria

Develop the configuration and quantity of X-ray booths and equipment required to support the maximum work load passing through the work station. Develop semi-automatic handling equipment required for loading, manipulating and unloading the X-ray booths.

#### b. Research Conclusions

- Research disclosed that this basic X-ray equipment is available but requires modi fication for automation.
- Prototype equipment must be designed and tested.
- Loading and unloading devices are available and can be purchased on the domestic market. This equipment will need modification to suit the facility.
- In the facilities visited during the course of this study, X-ray work stations were excluded from automation.

#### c. Feasibility

 It was determined that an X-ray work station can be operated semi-automatically. A conceptual design is available with specifications in the machine concept section of this document.

#### 14. Surface Preparation and Coating

#### a. Criteria

- Cleaning-develop a semi-automatic internal and external surface preparation system for pipe before the fabrication process is complete.
- Coating-develop a semi-automatic internal and external coating system for pipe before the fabrication process is complete.

#### b. Research

- External pipe cleaning machines are available from both domestic and foreign suppliers. The machines studied varied in configuration. Some have the capability of processing four (4) twenty (20) foot long pipes at one time.
- Internal pipe cleaning systems are also available
- Research pointed out that existing internal and external cleaning systems are treated as

- two separate work stations. The internal systems seen were not automated.
- External pipe paint system are available. They are automated and positioned adjacent to or in the near proximity of the external blasting machines.
- Internal coating is applied manually.

#### c. Feasibility

- It was determined that the equipment necessary for external blasting is available. Through engineering modification, it is feasible to blast internal and external pipe sections automatically. A prototype machine for internal and external blasting. must be designed and tested.
- Concept drawings and specifications are available in the machine concept section of this document.
- The same situation exists with internal and external painting. Prototype equipment must be designed and tested for automating the cleaning process as well as the painting process.

#### 15. Specialty Area

#### a. Criteria

Develop an area by selecting machines, tools and handling equipment for processing specialty items of a configuration and volume not suitable for automatic or semi-automatic processing. This specialty area would be part of the Pipe Shop, and its location should be accessible to the automatic conveying system. This would provide a cost effective utilization of auto cutting end preparation-bending, hole cutting, X-ray equipment, etc.

#### b. Research Conclusions

- The equipment requirements for a specialty work area are available as production equipment.
- The handling and manipulation of the work piece in this work station is presently accomplished manually.

#### c. Feasibility

- It is feasible to locate this work station where, by prefabrication, sub-assemblies can be transported to this work station by the automatic conveying system.
- The selection of special manipulators can improve efficiency in this area.
- Prototype manipulators must be designed and tested.

#### 16. Final Product Temporary Storage

#### a. Criteria

Develop a system whereby fabrication pipe and specialty items can be palletized and stored in a racking system in usage order until required for shipboard installation. Provide an automatic locator system to be used for accountability and retrieval.

#### b. Research Conclusions

 Temporary storage areas have been seen at most of the yards visited during the process of this study. Most of the equipment required is available and can be purchased. Extensive modifications, however, would be required.

c. Feasibility

• The problem with this area is that the storage system must be designed in the conifiguration necessary to work with the production criteria of the specific shipyard. For example, if a certain shipyard installs pipe in sections prior to hull erection, the temporary storage requirements are different from installing pipe systems after hull erection is completed.

• Final product temporary storage as outlined in the criteria is feasible. Prototype equipment must be designed and tested.

#### 17. Transportation and Handling of Final Product to Installation Site

a. Criteria

Select and/or develop cost effective transportation and handling equipment for the selection, picking up, transporting and delivery of fabricated pipe and specialty items to the installation

#### b. Research Conclusions

• The equipment required to support this function is available for purchase.

• Selection must be done with consideration given to the design of the temporary storage

c. Feasibility

Based on research, it was determined that the transportation system is feasible.

#### 18. Software

a. Criteria

Develop a software package to operate this system that would have the capability of preparing pipe detail drawings. As these drawings are being prepared, the program should select the concurrent preparation of bills of material, shop production schedules, material flow schedules, cutting lists, assembly marking and bending data, machine loading schedules and final disposition and delivery schedules. Several "stand alone" but integrated software packages, to suit the level of automation and types of equipment eventually selected, will probably be required. The implementation of the required software will require complete application capability which is available at most major ship yards.

#### b. Research Conclusions

• Software packages are available and can be purchased from foreign suppliers.

 The Maritime Administration has funded a feasibility contract to Newport News Shipbuilding and Drydock Company for the development of a software package which would provide engineering-including digitizing-in support of the automated design system.

c. Feasibility

- Ž A software system meeting the criteria is
- A software system developed by Mitsui Engineering and Shipbuilding Company

Limited is included in Section III of this document to illustrate the scope and requirements

#### D. Anticipated Benefits

The major benefits anticipated through the development of this project fall into the following area.

1. Excessive Handling

2. Fitting 3. Welding

4. Cleaning and Coating

5. Labor Expense

6. Process Flow Time

Using a LASH ship as a base, we estimate the percentage saving for each of the following items.

#### REDUCTION PER SHIPSET

1. Handling Man-hours 68 percent 55 percent 2. Fitting Man-hours 35 percent 3. Welding Man-hours 4. Cleaning Man-hours 79 percent 5. Coating Man-hours 86 percent

Using these percentages as a base, it is conceivable that Avondale could fabricate all ship piping systems for 45,000 man-hours compared to 75,000 man-hour cost. This is an overall reduction of approximately 39.8 percent per shipset.

#### E. On-Site Facility Surveys

1. On-site Surveys of Foreign Facilities

**FACILITY** LOCATION Dormagen, West Germany Bayer AG Chantiers De L'Atlantique St. Nazzaire, France Chantiers Di Castellammare Naples, Italy Di Sabin

Chantiere Di Monfalcone Trieste, Italy Nagoya, Japan Chita Shipyard (IHI) ESAB-HÉBE Company Hallsberg, Sweden Howaldtswerke-Deutsche Keil, West Germany

Werdt (HDW) Ishikawajima-Harima Heavy Industries Italcantieri-Cantiere De Geneva, Italy

Kockums AB Larikka Company (T-Drill Company)

Messer-Greishiem Mitsui Chiba Yard Mitsui Engineering&

Geneva-Sestri

Shipbuilding Co. Heinrich J. P. Muhlham Co.

Nippon-Kokan Oxytechnik Rauma Repola Shipyard

Wartsila Works

Tokyo, Japan

Malmo, Sweden Vaasa, Finland

Frankfurt, West Germany Chiba. Japan Tokyo, Japan

Bremen, West Germany Nagoya, Japan Frankfurt, West Germany Rauma, Finland Ylvieska, Finland

2. On-site Surveys of Domestic Facilities **FACILITY** LOCATION

Babcox/Wilcox, Inc. West Point, Mississippi

Bath Iron Works Corporation Bath, Maine Westminister, California Conrac Corporation, Tool

Division Cypress Welding Equipment

co. E. L Dupont Company E. I. Dupont Company Houston, Texas

Albany, Georgia Orange, Texas

Fairfield Machine Company Gaido-Lingle Company, Inc. Houston. Texas General Dynamics Corporation Quincy Shipbuilding Div. Ingalls Shipbuilding
Division of Litton Industries National Steel & Shipbuilding Co.
Newport News Shipbuilding and Dry Dock Porta Tools, Division of DND Corp.
Benjamin F. Shaw Co.
Southeast Fabricators Co.
Southwest Fabricating & Welding Co. W. K. Stamets Company Steffan Manufacturing Corp. Texas Pipe Bending Co. Todd Shipbuilding Corp.

Columbiana, Ohio Quincy, Massachusetts Pascagoula, Mississippi San Diego, Califomia Newport News, Virginia Houston, Texas Laurens, South Carolina Baton Rouge, Louisiana Houston, Texas


> Columbiana, Ohio Salem, Ohio Houston, Texas San Pedro, California

## **Section 11**


### **Section II**

Proposed Semi-automatic Pipe Fabrication Facility INDEX

- A.General
- B. Basic and Principal Features
- C. General Condition
- D. Actual/Proposed Time Comparison
- E. Equipment Requirement
- F. Plan View of Pipe Fabrication Facility
- G. Isometric Layout of Pipe Fabrication Facility
- H. Illustration of Pipe Fabrication Process
- I. Production Flow and Production Rate of Pipe Fabrication Facility
- J. Specification of Equipment and Machines with Concept Drawings



Manual pipe fabrication facility.



Semi-automatic pipe fabrication facility.

#### A. General

This section is dedicated to the conceptual design of the proposed semi-automatic pipe fabrication facility. Included are specifications and machine concept drawings which we believe are essential.

Avondale Shipyards' existing Pipe Shop was used as the base during the development planning required to produce the facility layout, fabrication sequence, production flow and production rate.

#### B. Basic and Principal Features

- 1. The basic idea in studying and planning this proposed pipe processing system is as follows:
  - a. This system is to be an integrated processing line with automation.
  - b. In the planning of this new semi-automatic Pipe Shop, great emphasis was placed on the automation of welding and a handling system that does not use cranes.
  - c. Concerning the effects of automation, the aspects of not only saving man-hours but also standardizing fabrication methods, improving fabrication precision and achieving centralized control of scheduling and material handling should be considered.
- 2. The principal features of the equipment to be installed in the new semi-automatic Pipe Shop are as follows:
  - a. A Surface preparation system for raw material. The internal side of the-pipe would be cleaned automatically in a closed cabinet by the use of a shot blasting lance. The external surface would be blasted using a blasting device located inside the closed cabinet.
  - b. An automatic marking, measuring and cutting system. Two kinds of cutting machines would be used depending on the diameter of the pipe. For pipes 1½ to 10 inches in diameter, machine cutting would be used. For pipes 12 to 24 inches, plasma or gas cutting would be applied with consideration given to the versatile use of the material. All of the work, from bringing in pipes to taking away scrap pipes, would be automated in accordance with the machine instruction system.
  - c. A flange fitting and welding system.
    - Four kinds of automatic welding machines would be used depending on the size and types of flanges. For steel slip on type flanges of 2 to 10 inches in diameter, a push button flange fitting and welding machine would be used. For stainless steel and non-ferrous metal flanges of 2 to 10 inches in diameter, TIG welding. Butt flanges with consumable insert rings would be used to save the time required for exchanging filler wires depending on the flange material. For weld neck flanges on 2 to 10 inch pipe diameters, one side plasma arc welding with back shielding gas would be used to obtain high quality weld joints that will pass the stringent X-ray inspection. For steel flanges of 12 to 24 inch diameter, gas metal arc welding processes would be utilized. In these welding machines, positioning of welding torches before welding would be done manually if necessary—but,

- during welding, it would be done automatically by arc voltage controls and sensing groove detectors.
- d. A bending system with suitable loading and unloading device.

Three types of cold benders coupled with automatic pipe loader and unloader would be used-4 inch, 8 inch and 12 inch flange on benders for pipe up to 4 inch, 8 inch and 12 inch diameter . . . each equipped with punch card machine instruction devices. For extra heavy wall pipe and large diameter pipe, a hot bending process would be used.

e. An assembling and welding system. for elbow and branch pipe.

Fitting and welding of branch pipe to main pipe over 14 inches in diameter would be processed manually. A prototype 90 degree branch welding device has been developed proving the feasibility of semi-automatic welding of branch pipe to main body pipe. A production model of the 90 degree branch welder can be manufactured. For fitting of branch pipe to main pipe, a branch pipe positioner would be loaded manually. Branch pipe from storage would be set to main pipe in the suitable position. A series of this movement would be controlled by push button operation. Included with the 90 degree branch welder is a hole cutting device which is push button controlled and semi-automatic, with quick select burning systems. Also designed into this equipment are 40 degree and 60 degree burning and welding of branches 12 to 24 inches in diameter with semiautomatic push button control for load manipulating, burning and welding. Concept drawings are available. For fitting of elbow to straight pipe, an elbow positioner and welding manipulator have been designed. A series of the movement from picking up the elbow in elbow storage to fitting the elbow in a suitable position would be semi-automatically controlled by push button operation. Welding of one end butt joint of the elbow would be semi-automatically carried out with pipe rotation.

f. Various types of welding positioners and manipulators.

The following types of welding positioners and manipulators are designed to realize easy welding and to improve the efficiency and quality of the welding work.

- One set of GMA flange welding machines for short pieces less than 36 inches in length.
- Universal welding positioner with GMA semi-automatic welder.
- Pipe welding elbow fitting devices for pipes 2 to 30 inches in diameter.
- Pipe rotation and welding manipulators for butt welding of pipe.
- X-ray facilities.
- Two sets of X-ray facilities are proved. One is for 2 to 10 inch pipe, and the other for 12 to 24 inch pipe. The X-ray generator is movable,

while the inspected pipe would be fixed on the pipe carrier. The X-ray generator can be easily set by hand with the assistance of a hand type manipulator.

h. Handling system.

In order to save man-hours and secure work safety, the plan is to use cranes as little as possible. For this purpose, the machines would be arranged in the pipe processing order with conveyers provided in the shop for handling the pipe. These conveyers would operate at safe speeds automatically, stopping at the designated work stations for removing pipe from the conveyer by instructions from cards or the select switch. The following devices would be provided to limit the use of cranes as much as possible:

Ž Automatic pipe loaders for benders.

- Pipe unloaders for removing bent pipe from benders.
- Elbow positioners for fitting elbows to pipe.
- Branch pipe positioners for fitting branch pipe to main pipe.
- Motorized dollies for transporting complete pipe assemblies.

#### C. General Condition

This system shall perform under the following conditions.

1. Pipe

Diameter: 1½ through 24 inches Length: Maximum single random ASTM A53 Material: Carbon Steel Carbon Steel ASTM A106 Carbon Steel ASTM A135 Alloy Steel ASTM A335 Stainless Steel ASTM A312 Copper ASTM B42 Copper Nickel ASTM B466 &

MIL-T-16420 Wall Thickness: Schedule 40 (STD), Schedule 80

(XS) . Flanges

Diameter: 1½ through 24 inches

Type Slip on welding steel pipe flanges ANSI B16.5 150 LB, 300 LB,

600 LB and 900 LB.

Socket welding steel pipe flanges ANSI B 16.5 600 LB, 900 LB and

1,500 LB.

Butt welding steel pipe flanges ANSI B16.5 600 LB, 900 LB and

1.500 LB.

Slip on brazing copper pipe flanges ANSI B16.5 150 LB and 300 LB.

Bronze Flanges MIL-F-20042 Steel Flanges MIL-F-20670

3. Daily Production Rate

Material	Steel	Non-ferrous	Pcs./Day
Size	Pipe	Metal Pipe	Total
1½ to 10"	66 pcs.	54 pcs:	120 pcs.
12 to 24"	15 pcs.	15 pcs.	30 pcs.
TO	TAL	•	150 pcs.

Figures are estimated. For details, refer to "production flow and production rate." Working hours per day-8 hours.

#### 4. Number of Workers

The number of workers needed to operate a semiautomatic pipe fabrication, shop is estimated as follows.

Section	Number of Workers
Fabrication:	
Machine Operation	12
Welding	10
Fitting	10
Others (including supervision)	7
Material Preparation	3
Handling and Transporting in the	
Shop	3
Sorting and Palletizing	3
TOTAL	48 men
The above figure is estimated cons	sidering the fac

The above figure is estimated considering the fact that the shop is operated by trained and qualified workers.

#### D. Actual/Proposed Time Comparison

The following matrix compares nine functions. The existing operation was time studied at Avondale Shipyards' Pipe Shop.

The proposed operation is an actual cycle time utilizing automation to perform the same tasks. It must be noted that this comparison was made at two different places-therefore, it is not a single facility study. The study points out, however, the tremendous savings which can be attained by automating pipe fabrication facilities. The time measured was that required to load the machine, process the work piece, unload the machine. All other operations were omitted.


machine. All other operations wer	Proposed	Existing
<ol> <li>Pipe Storage Rack         Cycle Time         Input Data         <ul> <li>Pipe Diameter</li> <li>Pipe Thickness</li> </ul> </li> </ol>	1.5 Min.	
2. Auto Punching Cycle Time Input Data Punching Position Punching Letters	2 Min.	5 Min.
3. Auto Marking Cycle Time Input Data Pipe Diameter Marking Positions	2 Min.	10 Min.
4. Auto Cutting Cycle Time Input Data Pipe Diameter Cutting Position Cutting Shapes	2 Min.	10 Min.
Sorting Destinations  5. Auto Flange Fitting/Weld Cycle Time (Including Weld) Input Data Position of Flange Holes Welding space	5 Min.	25 Min.


**Tack Welding Conditions** Welding Conditions
Sorting Destinations 6. Butt Welding
Cycle Time *30* Min. 6 Min. Input Data Fitting Position
Welding Conditions 7. Bevel Cutting 4 Min. 10 Min. Cycle Time Input Data Cutting Position
Cutting Speed
8. Pipe Bending 4.5 Min. 10 Min. Cycle Time
(2 Bent Pipe) Input Data Angles Planes Positions Flange Hole Pitch Diameter
9. Branch Pipe Welding
Cycle Time
Input Data 10 Min. 30 Min. Fitting Position
Welding Conditions
TOTAL 37 Min. 140 140 Min.


NOTE: Samples taken on 4 inch diameter standard pipe. .  $1\ 6\ 0\ w\ a\ 1\ 1$  .


E. Equipment Requirement Mark Name of System and Machine	Remarks		
1 Storage System for Raw Material 1-1 Elevator Selector Carriage (For Live Storage Racks) 1-2 Live Stock Rack (1½" to 6") 1-3 Live Storage Rack (8" to 10") 14 Live Storage Rack 1-5 Feed Table 1-6 Field Pipe Storage 1-7 Large Pipe Storage (Crane Loaded and Unloaded)  2 Surface Preparation System for Raw Material	Make Make Make Make Make Make	Branches (12" to 24")  9-2 High Elevated Elbow Welder (Sub-sub Assembly) (2" to 12")  9-3 Cypress Hole Cutting and Welder Branches (2" to 14") 90 Degree  9-4 Final Assembly (Area)	Research and Develop/ Available Research and Develop/ Research and
2-1 Automatic Shot B1asting and Cleaning Machine (4" x 24") 2-2 Automatic Painting Equipment 2-3 Automatic Drying Equipment	Purchase and Modify Purchase and Modify Purchase and Modify	10 Various Types of Positioners, Manipulators and Welding Equipment 10-1 Double Rotators Parallel with Common Welder or Tacker (Elbow	Develop/
3 Automatic Measuring, Cutting and Edge Preparation System 3-1 Edge Preparation Machine (2" to 10") 3-2 Contouring Machine (2" to 14") (Plasma/Gas) 3-3 Cutting Machine (1½" to 14") 34 Contour Machine (8" to 24") (Plasma/Gas)	Make Available Purchase Purchase	10-2 Manipulator  10-3 Elbow Rotator and Joint Welder (18" to 30")  10-4 Positioner and Fit-up Rotator	Available Purchase and Modify Purchase Purchase
4 Marking System 4-1 Automatic Marking Machine	Make	Elbows (2" to 12") 10-6 Pipe Rotator and Welder 2	Available Available
5 Flange Fitting and Welding Device 5-1 Flange Fitting and Welding Device (2" to 10") 5-2 Flange Welding Machine	Purchase and Modify Purchase and Modify	10-7 Automatic Flange Welding	Purchase
(10" to 24") 6 Flange Finishing Device 6-1 Flange Finishing Machine (2" to 10")	Purchase	•	Research and Develop/ Available
7 Bending System 7-1 4" Pipe Bender 7-2 8" Pipe Bender 7-312" Pipe Bender	Purchase Purchase and Modify Purchase and Modify	11-3 Manipulator 11-4 X-ray Booth (12" to 24") 11-5 Conveyer (Pip Carrier) 11-6 Manipulator 11-7 Scissor Jack	Available Make Available Available la bl Purchase Available
7-4 Hot Slab 7-5 Storage Slab 7-6 Heating Equipment 7-7 Sand Container and Machine	Available Available Available Available		Purchase Make Purchase and Modify
8 Contour Cutting 8-1 Contour Machine (2" to 10") (Plasma/Gas)	Available	Table (Typical)	Purchase and Modify
		13-2 Pipe Threading Machine (3" to 12") 13-3 Stone Saw	Available Available Available Available

e










PIPE SINDAGE RACK ---

Illustration of Pipe Fabrication Process for Pipe Shop Peoposal

29



NOTES:

I. THIS IS AN EXAMPLE ARRANGED TO REFER:

A. FIGURES ON ARROWS INDICATE THE QUANTITY OF

EACH WORK PER DAY.

B. THIS IS BASED ON THE ASSUMPTION THAT

TWO COMPLETED PIPES ARE PROCESSED FROM

ONE RAW MATERIAL.

Production Flow and Production Rate of Pipe Shop Proposal

## Specification of Equipment and Machines with Concept

Each specification and concept drawing has been assigned a number. This number is a locator number which is identical to the equipment number shown on the plan view and isometric layout of the Pipe Shop, Drawing 031-M76-8-2, Sheets 11 and 12 respectively. The purpose of the numbering system is to provide the reader with a quick reference from the layouts to the detail conceptual drawings, or vice versa.

#### Elevator Type Storage

Number of Set:

Stored Pipe 8"-10" 11/2" - 6"

Nominal Size: Length: Single Random Kind of Pipe: 32(4 kinds x 8) Number of Pipe: 1208 (totally in case 1½ - 6" pipes only)

Function & Control

Up-down drive of pick-up device; rack and pinion drive by electric motor


Push-pull motion drive of pick-up device; pneumatic cylinder

Positioning of pick-up device; automatically by limit switch

Loading table; gravity fed-hydraulic-kick outs Pipes are loaded on the loading table by crane.

A pipe is selected out according to instructions of the pushbutton on the operation desk for the shot blasting machine.

Selected pipe on the skid is transported to roller conveyer by means of transferring device furnished in the elevator type storage.



29"

9'-6"

Elevator Type Storage Rack

12'-014

#### 1-2 Skid Type Storage

Number of Set

Stored Pipe

Nominal size: Length:

Number of Pipe: Function & Control

Area of skid

Pick up device:

3

12"/24" Random

16 (in case of 18")

20' X 26'

Driven by pneumatic cylinder. Pipes are

arranged on the skid according to the order to be processed a day. One pipe is taken out on the roller conveyer by pushing button. It is controlled from shot blasting machine.

Skid type storage with pick up device

#### 2- Surface Preparation System for Raw Material


#### 2-1 Automatic Shot Blasting Machine

By this method the internal and external pipe surfaces are blasted. When internal blasting is not required, by-pass the lance

Number of Set One:

Applied Pipe

Diameter 1½" - 24"
Length: Max. Random
Method Nozzle & Lance



Composition

Grits collector

Bucket elevator

Blast tank (two steps continuous work type) One
Abrasive hose and nozzle (Nozzle dia. 5/8)

Grit shield with sliding mechanism

Dust collector

Pipe feeding and ejecting device

Abrasive material

One
Set


One
Set
One
Set
One
Abrasive dia. 5/8)

Four
One
One
Steel grit

#### Function

Pipe is automatically fed to external blasting

cabinet on conveyer. At the point when the pipe enters the blasting cabinet the conveyer feed speed is semi-automatically matched to blasting speed and blasting begins. Blasting continues as pipe passes through the blasting cabinet.




When the pipe is in the position shown above, external blasting is completed. The conveyer and blasting function automatically stops. The appropriate lance is selected, positioned and fed through the inside of the pipe. Lance speed and blasting injection rate is matched to obtain specified surface preparation. After the lance has traveled the pipe length, internal blasting is complete, the lance is backed out and positioned in the lance rack automatically. The residual blast media is automatically discharged into the external blasting cabinet for recovery.

#### Operation

After the pipe on the conveyer is fed in the machine via push buttons and select switches from the operation desk, pipe setting and blasting work is done automatically.

Manual operation of each sequence via push button is also possible.




2-2 Painting Equipment

Internal coating is applied, if required, in the first step

of this process.

Number of Set One Applied Pipe

Diameter: 2" -36" Length: Max. Random



The pipe is positioned as shown above automatically with the leading end of the pipe just inside the spray booth. The spray lance is selected from the lance storage area and positioned automatically using push button controls. The lance travels through the pipe; spraying starts automatically using a limit switch; the lance travel speed is matched to spray system with variable preselect push button control for application on different types of coatings. When the lance passes through the work piece, spray starts as the lance is backed out, then returns to storage automatically.

When the lance is returned to storage, the external

coating system starts automatically. The pipe is carried through the spray booth on slat conveyer. Spraying starts automatically. If internal coating is not required, the internal coating process is bypassed.

#### Composition:

Spray booth

Airless spray system with two guns for external painting

Spray flange fitted with appropriate nozzles and travel mechanism for internal coatings.

Slat chain conveyer with drive system and push button control.

#### Function

Conveyer speed: 15 feet per minute

Airless spray system


Electro mechanical device for automatic controls. Pneumatic device lance storage.

#### 2-3 Drying Equipment


By adopting an infrared dry oven this process can be accomplished quickly and economically.

Number of Set One
Applied Pipe
Diameter: 2" -36"

Length: Max. Random



Painting Equipment



An infrared drying oven positioned the appropriate distance from the paint booth, fitted with push button controls and limit switches, bring he oven up to operation temperature employing speed control. Slat conveyer will cure the coating by the time the pipe passes through the oven.

A device is installed on the exit end of the oven to automatically stamp the pipe alloy identification on the pipe piece as it passes.

A touch up area is required for coating the pipe where it was resting on the slat conveyer. This is a manual operation.

Composition:

240 infrared panels

Operating

375 Deg. F Temperature: Slat Conveyer Speed: 15 feet/min.

Automatic controls: Electro/mechanical 3. Automatic Measuring, Cutting & Edge Preparation System.

3-1 Edge Preparation Machine (2"-10")

Number of Set:

Applied Pipe

2" -10" 2'-20'

Nominal Size Length: Material:

Carbon steel, alloy steel, stainless steel, copper-

nickel

Edge preparation method

Mechanical edge preparation by rotation of cutting tool with clamping of pipe.

Function & Control

Chucking: Automatic centering and chucking mechanism

Setting of cutting tool to pipe end:

Manually by handle


Machining By automatic cutting feed of cross head and tool post.

Changing of automatic feed speed:

Manually by lever

Operation

Push button and manually



Edge Preparation Machine

#### 3-2 Contouring Machine

This machine provides the versatility of contour cutting the various alloys with simultaneous beveling.

Number of Set: 3

Applied Pipe

Material: Carbon steel, stainless

steel, etc.

Diameter: 2"- 10"; 2"- 14"; 8"-24"

Thickness: .156 -.624 Length: 20 feet

Composition

Power source: Max. 500A (D.C. dropping charac-

teristics)

Secondary load voltage: 200V or 400V

Fume exhaust device Air compressor for plasma

Torch positioning device: manipulator, sensor,

guider consumable parts: electrode 2-4 hours. nozzle 1-3 hours.

Optional select standard gas cutting system.

Operation

The pipe fed from conveyer by push button shall be set and cut via push button controls.

#### 3-3 Cutting Machine

This machine automatically saws pipe to length leaving a square clean cut of which beveling will be applied at another work station.

Number of Set: One

Applied Pipe

Normal Size: 1½" - 14" Length: 2-20 Feet

Material Carbon steel, stainless

steel, copper, copper-

nickel, etc.

Cutting Method:

Mechanical cutting by means of high speed saw. Function & Control:

Measuring of cutting length:


Pipe is selected and positioned under saw in appropriate position by push button control using end stop preset by means of manual digital switch stopping pipe at desired length for cutting.

Scrap Pipe Removal:


By automatic scrap conveyer

Operation:

A series of automatic operations in accordance with the instructions of push button operation by the operator.



Typical contouring machine.



Typical saw type cutting machine.

#### 4 Automatic Marking Machine

The paint spray method of marking can be done on pipes of any material and the size of figures is changeable.

Number of Set: One

Applied Pipe

Diameter: 1½" -24"

Method

Paint spray method

Composition

Paint unit

Control box and electric solenoid valves

Moveable spray guns with two motors

Function


Figures from zero to nine can be marked as being arranged.


Control:

Number and size of figures are preset via select switches.

Figures are marked individually by keying in of respective buttons.

Automatic operation is possible in accordance with instructions from NC card from disk type cutting machine.







# Marking Machine

5 Flange Fitting & Welding

5-1 Flange Fitting & Welding Machine

This machine must be designed for semi-automatically fitting weld neck flanges as well as slip on flanges. The welding method shall be quick change automatic gas metal arc/or Tig as comportable materials involved.

Number of Set: One


Material: Steel, CR-MO Steel,

Stainless Steel, etc.

Diameter 2" -10" Length 2'-20'

5-1A TIG

Method (TIG)



Composition

Power source: D. C./A.C. 300A

Fixed type manipulator

Moveable type manipulator

Pipe support rollers with rotation mechanism Operation

Pipe and welding condition would be preset via select switches.

Torch positioning and welding are done automatically in the suitable condition by Arc Voltage controls and Auto groove detector after

setting manually via push button.

5-IB NC flange fitting & welding machine

This machine is specially designed for automatically fitting and welding pipe and flanges in accordance with the instruction of NC control desk.

Applied Pipe and Flange

Normal size: 2" - 10"
Length of Pipe: 2' - 20'
Material: Steel

Type of Flange: Slip on weld, 150 LB,

300 LB

Function & Control

Numerical control axes; 10 axes

Positioning of moveable saddle x 1

Positioning of flange bolt hole detector x 2

Positioning of jaws x 6

Differential angle of flange bolt holes between both sides x 1


Tacking and welding:

Automatic GMA welding machine


Fine adjusting of continuous welding is manually done, if necessary.

Operation

Pipe and flanges, conveyed through pipe cutting machine and flange storage and selector respectively, is automatically fitted and welded by this machine in accordance with instructions of NC card.



Typical flange welding machine.



Close up view of flange welding machine.

5-1 C Flange Storage & Selector

Number of Set One

Stored Flange

----

Normal Size:

2" -10"

Material:

Steel, CR-MO, Stainless

Steel, etc.

Type:

Slip on weld, 150 LB,

300 LB

Kind of flange:

18(9 kinds x 2)

Function & Control Loading flanges in storage:

Manually by using loading

jig and crane.


Taking out method:

Pushing by pneumatic

cylinder

Control: Automatic operation/

required flange is selected out in accordance with the instruction of NC card for NC flange fitting and welding machine.



Typical flange storage and selector device.

### 5-2A GMA Flange Welding Machine

By employing 4 torches-concurrent-work method the welding of inside and outside of flange on both sides is done simultaneously.


Number of set: One Applied Pipe and Flange

Material: Carbon Steel
Diameter: 12". 24"
Length: 3'-20'

Thickness: Weight class STD, XS

Method

4 torches-concurrent-work GMA Welding method



Fixed type manipulator with two welding torches, sensers and guides

Movable type manipulator with two welding torches, sensers and guides


Support rollers with rotation mechanism

Operation


Pipe feed and take-out work is done via push buttons

Electric current, voltage, welding speed and arc time are preset via select switches

Torch positioning and welding are done automatically in the suitable condition by mechanical guide sensers.



GMA Flange Welding Machine



5-2B Flange Fitting Machine

Number of set: One Applied Pipe and Flange

Nominal size: Length of Pipe:

Material of pipe

and flange: steel

Type of Flange: Slip on weld 150 LB & 300

Composition

Fix and moveable carriage, semi-auto GMA welding equipment for tack welding flange.

Function & Control Inserting flange in

chuck By exclusive hoist Chucking method: By electro-magnet chuck Adjusting jig: To be prepared for each

kind of flange. By only setting the flanges by using adjusting jig; the relative position of bolt holes between both flanges is mechanically in the same position and lip length is exactly

decided.

Tack-welding Manually by using semi-

automatic GMA welding

machines

Operation: By push-button and

manual

#### Flange Finishing 6

6-1 Flange Finishing Machine

> Number of Set One Applied Pipe and Flange - ]()" Nominal size: 1'-20' Length of Pipe:


Material: Steel, CR-MO Steel,

Stainless Steel, etc.

Slip on weld, 150 LB, 300 Type of Flange:

ĹB


By bore and face milling Finishing Method: cutter with pipe rotation




Control & Operation

Carriage is automatically positioned by detection of pipe length with limit switch. Setting of cutters is manually controlled.

Machining of inside welded part and cleaning of spatter is concurrenty earned out at both ends.



Typical flange finishing machine.



Close up view flage finishing machine.

7. Bending System with Loading & Unloading Devices

7-1A Automatic pipe loader

The machine is designed for automatically transporting and loading the pipe from the pipe skid to the suitable position of NC 4" pipe bender.

Number of Set:

Applied Pipe Nominal size: Length:

Shape: Straight without flange

Operation & Control

Automatic operation:


A series of movement is earned out in accordance with the preset sequence combined with NC 4"

bender. Positioning to catch size pipe by limit switches.

Manual operation: Control by using the push

button on the operation

desk.



Typical bending machine loading device.

7-IB NC\_4" pipe bender

This machine is designed to bend automatically the pipe in three dimensions in accordance with the instructions of numerical control combined with automatic pipe loader.

Number of Set One Applied Pipe and Flange 2"- 4" Nominal-size: 2'-20" Length of Pipe:

Shape of Pipe: Straight with/without

flange

.11- .34 inch Thickness of pipe:

Material of pipe

Carbon Steel, stainless & flange: steel, copper, copper-

nickel, etc.

Function & Control Numerical Control

4 axes-measuring pipe axes: feed length, rotation

angle of pipe, bending angle, and positioning of flange bolt hold detector.

2 steps changeable Bending speed: Approx. 2 x out dia. Bending:

(General)

Plug type and ball type Mandrel:

Pressure dia Chucking

Sliding type

Equipment For positioning and rotating of pipe. Furnished flange bolt hole detector.


Correction of spring back

Program input (NC card) or manual input by digital

switch.

Operation Automatic Operation

A series of three-bending (max.) is carried out according to the instructions of preset sequence and data input by NC card or NC tape.



Typical N.C. 4 inch bending machine.

Semi-automatic

Operation: One-bending is carried

out in accordance with the data input by digital

switch.

Manual Operation: Control by the push-

button on control

console.

7-2A Automatic Pipe Loader, 6" - 8"

This machine is similar to that of 7-1A

Number of Set: One Applied Pipe and Flange, - 8" Nominal:

Length of Pipe: 3'-20'

Shape: Straight with/without

flange

Same as 7-1A Operation:



Typical flange on bending machine.

7-2B NC 8" Pipe Bender

This machine is similar to that of 7-lB.

Number of Set: One

Applied Pipe and Flange, -8"

Nominal Size: 3'-20' Length of Pipe:

Shape of Pipe: straight with/without

flange

Thickness of Pipe: .12-.4 (General)

Material of Pipe

Carbon Steel, Stainless and Flange:

Steel, Copper, Copper

Nickel, etc.

Function and

Control: Same as 7-1B.

7-3A Automatic pipe loader (8" - 12")

This machine is similar to that of 7-1A.

Number of Set

Applied Pipe and Flange - 12"

Nominal Size

Length of Pipe: 3 , - 2 0 ,

Straight with/without Shape:

flange

Operation Control: Same as 7-1A 7-3B NC 12" Pipe bender

This machine is similar to that of 7-lB

Number of Set: One

Applied Pipe and Flange / 12" Nominal Size:

3'-20' Length of Pipe:

Shape of Pipe: Straight with/without

flange

Thickness of Pipe: .138 -.495" (general)


Material of pipe &


flange: Carbon steel, stainless

steel, copper, copper-

nickel, etc.

Function, Control & Operation is the same as 7-1B.





- 4 Hot Bending System

This system is available and used mostly due to the low volume of pipe size requiring bending.

Number of Set One

Nominal Size: Over 6" Extra Heavy

Length: 2'-20'

Material: Carbon Steel, Stainless


Steel, Copper, Copper-

Nickel, Etc.

Composition: Furnace or other heat

source slab for securing pipe and making bend equipment for handling sand and pipe forming jigs and dies torches and radiant heat boxes and stress relieving

equipment.



Hot Bending System

8-1 Contouring Machine

This machine provides the versatility of contour cutting the various alloys with simultaneous beveling.

Number of Set: One

Applied Pipe

Material: Carbon Steel, Stainless

Steel, etc. 2" -10" Diameter .156" -.624" Thickness:

20 ' Length:

Composition:

Max. 500A (D.C. dropping Power source:

characteristics)

Secondary load voltage:

200Vor 400V

Fume exhaust device Air compressor for plasma

Torch positioning

device: Manipulator, senser,

guider

Consumable Parts: Electrode 2-4 hours

Nozzle 1-3 hours

Optional select standard gas cutting system.

Operation:

The pipe fed from conveyer by push button shall be set and cut via push button controls. This machine is typical of item 3-2.

- 9 Elbow and branch pipe assembly, welding system
- 9-1 Semi-Automatic 40 deg. -60 deg. hole burning and welding machine.

Branch pipe piece is processed on contour cutting machines (3-2 and 3-4). Branch pipe is conveyed to branch pipe storage. Main body pipe is selected and positioned in 40 deg. -60 deg. hole burning machine. The machine automatically cuts the main pipe hole whale calculating the contour with analogue control.

Applied Pipe:

2" - 24". Nominal Size: 2'-20" Length:

Material: Carbon Steel, Alloy Steel,

Stainless Steel, Etc.

Cutting Method: Plasma cutting with pipe

rotation and torch

movement

Composition: Chuck equipment with

cutting torch pipe support roller.

"Function & Control Main Pipe Hole Cutting





Joint Angle 40 Deg. -60 Deg. -90 Deg. -150 Deg. Contour Computing Method: Analogue Control Beveling Control of Torch

Constant Angle Beveling: Inclination angle of torch is constantly

fixed. **Constant Point Beveling** 

> Torch is always aimed toward the intersecting point of main and branch pipe's center line.


> Setting Valve: By dial main pipe diameter. branch pipe diameter joint angle.

Hole Cutting Operation

Main pipe is set by push button control. After setting the required data and positioning the cutting torch is automatically accomplished.

Fitting and Welding Operation:

Branch pipe is positioned on the main pipe by means of branch pipe positioner by push button control; tack welding is manual; welding is manual.



Semi automatic branch pipe assembling & welding machine

## 9-2 High Elevated Elbow Welder 2" -12"

This device is used to semi-automatically fit and weld pipe to pipe and pipe to elbow.

Number of Set One

Applied Pipe, Elbow

Material: All materials

Diameter

Max. 20'

Length: Composition

Fixed pipe chuck with jack-up

Moveable elbow chuck with jack-up


Moveable support roller

Operation-Rotator

Support rollers are moveable push button control Pipe chuck and elbow chuck are operated by push button control

Operation-Welding

Tacking is manual; welding is semi-automatic submerged ark, manually positioning the welding gun to the groove. The welding process and rotating device is push button controlled and carried out automatically.



Pipe rotator and elbow fitting device (2".24")

# 9-3 Cypress Hole Cutting and Welder Branches (2" - 24") 90 Deg.

This machine is designed for automatically burning the hole and semi-automatically fitting and welding 90 Deg. branch pipe to main body pipe.

Number of Set: One

Applied Pipe Nominal Size: 2" -24"

Length of Main

Pipe: 2'-20' Material: All

Composition:

Branch Storage Area


Chuck equipment with cutting torch

Pipe support

Chuck equipment with welding torch


Function and Control:

Branch pipe is cut on contouring machine (3-2) Bevel is suitable for saddle on fitting, 40 deg. top. 20 deg. bottom.



Saddle on branch positioned on main pipe.

Main body pipe is selected and set in appropriate position in machine automatically by push button control. Cutting torch is set in appropriate position and hole cutting is anticipated and completed via push button control. Torch angle is maintained at 90 deg. to to horizontal plane of main body pipe using plasma or gas cutting system.



Main body pipe is in fixed position, torch makes 360 deg. turn holding 90 deg. to horizontal plane following external shape of main body providing the contour cut. After the hole is cut in main body the branch pipe is selected from branch storage and set in saddle on position by means of the branch pipe manipulator via push button control.

Branch pipe is tacked to main body manually.


The welding head is set in position, torch is positioned to groove semi-automatically, weld is done automatically via push button controls..


# 9-4 Final Assembly area

The final assembly area is equipped withjigs, fixtures, positioners and manipulators for fitting the sub-sub assemblies and sub-assembly pieces.

The sub-sub assemblies and sub-assemblies are fabriicated at semi-automatic work station then conveyed to the final assembly area via push button select controls.

The main body pipe is set in fixture etc. manually. The main body, sub-assemblies and sub-sub assemblies are all pre fabricated. The fitting and tacking process is manual. Welding is accomplished semi-automatically when possible. Some pipe spools are of a configuration not conducive to automation. These items are manually welded.







Cypress hole cutting and welder-branches (2" - 14") 90°

10 Various Types of Positioners, Manipulators and Welding Equipment


> This equipment is placed at specific locations throughout the production line. Each item is fitted with kickout for selecting and bringing the pipe to the machine via push button controls.



6-10



Item 10-5—High boy rotator with 2-variable support dollies elbows 2"-12"



Item 10-6—Pipe rotator and welder 2 double dollies

# 11 X-Ray Facilities

As the X-ray generator is fixed at the top of the magic-hand manipulator and as the film cover is magnet type, the setting work is quite easy on keeping pipe fixed.

on keeping pipe fixed. Number of Set: 2

Method

Double walls double image method 4" Double walls single image method 4"

Composition

X-ray booth with lead and concrete walls

X-ray controller

X-ray generator and magic-hand manipulator

Overhead motorized chain conveyer


Function

Exposure time A B 2 min. 1 min.
Emission distance 2 feet 2 feet Film density 2

Operation

The most suitable condition with the least time film and generator setting work is manually done with the device.

X-ray operation is done at the control room via push buttons and select switches.



X-ray facilities

# 11-7 Motorized Scissor Jack Dolly

This is the equipment for transporting the finished

Number of set: Four (4)

Applied Pipe Shape: All shapes/straight, bent,

flanged, branched


Function & Control

Loaded capacity: 2000# 3'- 450'/min. Speed: By motor Drive:

Operation

Loading and unloading of pipes are done by means

of crane.



#### 12 Pipe Handling System

#### Roller Conveyer 12-1

This is the conveyer which is designed for feeding the raw material pipe.

Typical:

One is 10 feet in length from storage for raw material to shot blasting machine. 11/2" - 24"

Applied Pipe Size:

Function & Control

Drive of the feed

roller:


Chain drive through electric geared motor Speed of feed

variable: 50 - 150 feet/min

Control: In general, the conveyer is operated all the time. In case of detecting a pipe by the sensor or the pipe stopper, the conveyer is automatically stopped.

Operation

Push button control by operator



## 12-2 Traverser

This equipment is for traversing the pipe from the feed conveyer to the 12" -24" processing line.

Tvpical

Applied Pipe Size: Cross Over


Feeding

1½ - 24" Rail runner Kick-out Stop position

control: By pipe stop kick-out

Operation

Push button control by operator.



12-3 Pipe Kick Out for Conveyer

Typical

Applied Pipe

Nominal Size: Length: 1½" -24" 2'-20'

Function & Control


Drive: Pipe Stop:

Pneumatic Cylinder Mechanical Detection by Limit Switch


Control: Autor

Automatic Control when the pipe stop detects a pipe, the conveyer stops and the apparatus is energized to remove a pipe from the conveyer. In case shown in photograph, apparatus is operated by instruction, push button control at machine for pipe

selection.



Typical pipe roller conveyer for transporting pipe from storage to the various work stations.



Three pipes in holding area held by typical conveyer pipe kick out ready for selection. Machine operator can push button; pipe moves to feed roller conveyer; roller conveyer moves pipe to machine for processing.

# 12-4 Pipe Kick-Out for Transfer Tables

This device is for passing pipe from main feed roller conveyer to machine for processing or vice versa. Pipe piece will be of varying length and may have to be retrieved from slat or plate type conveyer.

Typical

Applied Pipe

11/2" - 24" Nominal Size: Length: 2'-20"

Shape:

With or Without Flange


Function and Control

Drive: Pneumatic Cylinder Control: In case of passing the pipe

to the next work station the device is closed.

Operation: Push button control from

the work station.



Typical kick out device.

# 12-5 Chain Conveyer for 1½" -24" Completed Pipe or

Pipe Being Processed

Typical '

Applied Pipe


1½"- 24" Nominal Size: Length 3'-20'

Shape with or without flange Function & Control

Drive: Speed:

Control:

Electric geared motor Approx. 3'-50' Automatic control.In general the conveyer is operated by push button control. When the pipe stopper detects pipe, the conveyer is automatically stopped.



Typical Section

# 12-7 Automatic Flange Welding Machine for Short Pieces (12" - 24")


Very short pipe with flange, which would not be worked at the flange welding machine (5-1 or 5-2), are welded by this machine.

Number of Set: One Applied Pipe and Flange

Material: Carbon Steel
Diameter: 42"-24"

Length: Method

GMA automatic weld.



Composition

Torch positioning manipulator with guide sensor Pipe clamping and rotating device


GMA Welder

Operation

Electric current, voltage, welding speed and arc time are preset via select switches.

One side of pipe-elbow butt welding can be done semi-automatic elbow assembling & welding machine-( 104 or 10-5) and the other side of it shall be done manually after both flanges are welded by this machine.

The torch positioning is done manually via push buttons and welding automatically by mechanical guide sensors.



Typical automatic flange welding machine for short pieces (12" - 24")


13 Specialty Area

This area is comprised of machines, tools and handling equipment for processing items of configuration and volume not suitable for automation.


Number of Set: One

Method: The majority of this work

is manual



Manual fitting and welding of condenser head



Manual fitting semi-automatic welding reducer to pipe piece

Composition:


Pipe,,threading machine

Pipe threading machine 3"- 12"

Stone Saw Band Saw

Various Welding Machines

Various Holding Jigs Various Manipulators



Manual fitting and welding small part to main body pipe



Manual fitting and welding reducer to main pipe piece

# **Section III**

# **Section III**

Computer Software System INDEX

- A. Summary
- B. General
- C. GPS (Graphic Piping System)
- D. Pipe Shop Production Control System
- E. Palletizing System
- F. Computer Software Outputs
- G. Computer Configuration to Accomplish Software Package

# A. Summary

This section is dedicated to computer software package information. The system outline, used as a sample, was developed by Mitsui Engineering and Shipbuilding Co. LTD..


There are several good software package systems presently on the market or under development. All of these systems have a common base utilizing somewhat different methods. The common base is the engineering part of the software system. The MAPS system includes three principal features which we consider essential to the operation of a pipe fabrication facility as previously outlined in Section II.

• Pipe Detail Drawings

• Pipe Shop Production Control System

Palletizing System

A list of software suppliers is available in Section V of this document. Included in the list is the Newport News Shipbuilding and Dry Dock Company system which is currently under development. Also included is the Kockums Shipbuilding Company (System "Q" and "Steer Bear") system, which is excellent.



M-II-B ased for GPS in the computer software package

# B. General

The computer software package developed by MES, now in successful operation at Mitsui's Chiba Works, is the system aided by computer to obtain information necessary for fabricating instruction of pipe pieces. material preparation, pipe shop production control and palletizing work.

The pipe fabrication shop and palletizing work cannot be operated smoothly and effectively without the support of this system.

For your new pipe shop project, we propose this computer software package as software to a semi-automatic pipe fabrication shop mentioned.

The proposed computer software package is composed of the following three (3) systems.

# GPS (GRAPHIC PIPING SYSTEM)

From pipe arrangement drawings, necessary data are input by man-machine communication through the medium of graphic display coupled with exclusive mini-computer, which, in turn, calculates the shape and dimension of each pipe piece and furnishes the numerical information for fabrication of various kinds of pipe pieces.

The output of this system can be converted to the form best suited to the facilities and working method of the pipe shop, i.e., in the form of order card for NC equipments and in the form of numerical list for other equipments and manual work.

Furthermore, valve, piece, cock, bolt, nut, packing and other small attachments to pipe are also input together with pipe through graphic display.

These data are stored in the master file and are utilized by palletting system.

Pipe Shop Production Control System

Using the master file created by GPS as source data, host computer furnishes information required for the production control in the pipe shop such as scheduling of cutting date, cutting plan, material control and load balance.

## Pal1etting System


For smooth progress of outfitting work, it becomes necessary to timely collect and deliver outfitting materials such as pipes, valves, cocks, pieces, bolts, nuts, packing, etc. to installation site. For the sake of fulfillment of this necessity, we developed a material flow control system called "Palletting System."

In GPS. from detail drawings, necessary information for palletting is input and filed in the master file. They are edited by host computer and timely furnished to the prefabrication shop, materials purchasing department, materials management department and transportation control center, converting to the order forms met with requirement of each department.


Fig. II-1 Photograph of graphic display MA CSGRAPH General flow chart of the proposed computer software package is shown in Fig. 11-2.

MAPS MITSUI ENGINEERING & SHIPBUILDING CO., LTD., CHIBA WORKS

Fig. 11-2 General flow chart of the proposed computer software package



MAPS MITSUI ENGINEERING & SHIPBUILDING CO., LTD., CHIBA WORKS



## C. GPS (GRAPHIC PIPING SYSTEM)

For this system, mini-computer with graphic display processor is provided. (Refer to computer configuration in chapter 6.)

As one of the most effective methods to assist the designer in feeding data into computer, the graphic display coupled with exclusive mini-computer is used instead of big computer. In this system, the designer can give data to computer by man-machine communication through the medium of graphic display, light-pen and keyboard.

Therefore, filling in data sheets, card punching and verification can be eliminated.

The designer can get quick response from computer because of realtime interaction, and can easily modify the data on the spot.

This system is considered one of the latest practical application computer aided design system.

Process flow of this system is as follows;

At first, piping route is created on the graphic display screen from pipe arrangement drawing. On the other hand, piping specifications such as material, diameter, working pressure, working temperature, type of joints, coating, treatment, testing, etc. are coded for each pipe line from pipe specifications and filed by host computer as Pipe Line File.

The shipyards standards of fitting parts such as dimension, weight, cost code, etc. and working standards are also filed as Item Data File and Working Standard File, respectively.

Matching these data in the mini-computer, all informa-

tion necessary for pipe fabrication are calculated and stored in the master file, which are used as source data of the subsequent two systems; Pipe shop production control system and Palletting system.

Flow chart of procedure to feed data through graphic display is shown in Fig. II-3.

Numerical expression of pipe piece


In this software, not only graphic representation but also numerical expression is used to show the shape of pipe pieces.

In general, three dimensional shaped pipe shall be analyzed into straight length, girth length in bending corner, bending angle in plan and rotating angle in space, for instance, in Fig. II-4.

Computer analyzes the piping route on the graphic display screen into the above components, and they are arranged according to pipe fabrication procedure. Example of this arrangement is shown in Fig. II-5. Since information is given to workers in numerical expression as shown in the example, workers can easily perform their job such as marking, cutting, bending, assembling, etc. without any judgement, experience or good perception.

The relation between numerical expression and pipe fabrication procedure is shown in Fig. II-6. The bending process for any complicated shaped pipe with bender can be divided into three simple components of motion, feeding of pipe, rotating pipe, and bending pipe.

Therefore, so far as pipe processing is followed with numerical indication which consists of the above simple components, workers can easily perform their job without any comparison with graphic drawings.



59





Fig. 11-5 Numerical expression arranged according to pipe fabrication procedure



	OPERATION SEQUENCE	EXPRESSION ON PART PLAN
MARKING	193:301:346 1220 494 130 940 2160	193 301 346 100 1220 193 494 840 940 2160 90 (90)150
CUTTING	2160	193 301 346 100 1220 193 494 840 940 2160 90 (90)150
FLANGE FITTING AND WELDING	/! 2/60   7 Slip leigth) *1	193 301 346 100 1220 193 494 840 940 2160 90 (90)150
	FEED 20 (1931+7)	193 301 346 100 1220 193 494 840 940 2160 90 (90)150
	OBEND 301	193 301 346 100 1220 193 494 840 940 2160 90 (90)150
BEND	OFEED 346	193 301 346 100 1220 194 494 840 940 2160 90 (90)150
	ROTATE 70	193 301 346 100 1220 193 494 840 9.0 2160 90 (90)150
	BEND 100 VZZZZZZZZZZZZZZZZZZZZZZZZZZZZZZZZZZ	193 301 346 100 1220 193 494 840 940 2160 90 (90)150
FINISHED FORM		
NOTE:*	KD(Slip length)	

Fig. II-6 Relation between numerical expression and pipe fabrication procedure

# D. Pipe Shop Reduction Control System

For the production control of pipe shop, scheduling program and cutting plan output program are provided.

Fig. II-7 shows its flow chart.

The master file, processed and filed by GPS, is used as the source data for the two programs above. This system is run under the host computer.

The process flow of the scheduling program is as follows;

Calculation of how many days required for pipe piece fabrication for all pipe pieces in the master file.

Decision of the Cutting Date for each pipe piece.

(Remarks)

Cutting Date; The date when a pipe piece is started fabrication in the pipe shop.

Summing up total number of pipe pieces & required manhours for every cutting date.

Output of man-hour loading list.

Fig. II-8 & 9

The process flow of the cutting plan output program is as follows:




Fig. II-11, 12, 13& 14

plan.




Fig. II-7 Flow chart of pipe shop production control system

# E. Palletizing System

For smooth and effective progress of outfitting work, complete and timely supply of outfitting materials to installation site is required.

For this purpose, the new concept "Pallet Outfitting System" was introduced to the field of outfitting work. That is; The whole outfitting work of one (1) ship is divided into many working units by working place and time, and then these small working units are completed in an appropriate order under necessary information for every unit. One (1) working unit has its own pallet name and delivery date. All materials belonging to one (1) pallet name must be collected by its delivery date, independent of kinds of materials.

This material preparation work is carried out with the support of Palletting System which supplies necessary information for material collection with the aid of computer.

Using the master file created by GPS as source data, host computer outputs pallet tables for each kind of materials, such as pipes, valves, pieces, cocks, bolts, nuts, packing, etc.

The pallet table affords items necessary for palleting as shown below.

- Job order (ship number)
- Pallet name
- Delivery date, Fitting date
- List number, Order number, Drawing number
- Kind of type
- Article code
- · Quantity, Weight

Owing to the development of Palletting System, all outfitting materials are completely palletized without any missing parts and are supplied to installation site just in time, so that outlifting work can be done smoothly.

	SYSTEM	OUTPUTS	EXPLATION	SAMPLE;
		MAN-HOUR LOADING LIST & GRAPH	For ovory cutting date, total number of pipe pieces and required man-hours are shown.  This. indicates future working load in the pipe shop. in order to keep good load balance, this man-hour Ioading Can be modified by giving "Cutting Plan Control card" to computer.	Fig. 11-8 G Fig. 11-9)
		PIPE CUTTING	This list is output every working day. All pipes to be cutt on the day are printed out in this list according to cutting sequence decided by computer to minimize the scrap pipe and the time for exchanging machine tools.	Fig.ll -10
33	1'11'1: SHOP PRODUCTION CONTROL SYSTEM	MATERIAL LIST	According to "Pipe Cutting Plan", all materials used for fabrication of pipe pieces, such as pipes, flanges, elbows, reducers, sleeves, sockets, etc. are summed up classifying to cost accounting code, size, material, type, etc.	Fig. II-11 & Fig. II-12
		NC CARDS	Two kinds of numerical control cards(NC cards) are used as instructions to numerical control machines.  These cards are the outputs from computer in the same order as cutting sequence shown in "Pipe Cutting Plan".	Fig. 11-13

M A P S MITSUI ENGINEERING & SHIPBUILDING CO., LTD., CHIBA WORKS

	SYSTEM	OUTPUTS	NOT.I.VNV.T.TON	SAMPLE
	PIPE SHOP	I DENTIFICATION NUMBER	After a pipe piece is cut, this label, which is also the output, from computer, is put on it for identification such as ship number, pallet name, serial number, fabrication line and path, kind of treatment, etc.	Fig. I-14
	PRODUCTION CONTROL SYSTEM	NUMERICAL PIPE PIECE LIST WITH GRAPHIC REPRESENTATION	This list, which is output by COM (Computer Output Micro-film), is used for numerical instructions to workers, i.e., shop details containing all the necessary alpha-numeric information for cutting, fitting, bending, welding, painting, testing and identification This is provided for every pipe piece.	Fig. 11-15
67	PALLETT NG SYSTEM	PALLET TABLE	This table is used for collecting and delivering all articles by each pallet name. It contains palletting information such as delivery date, list number, order number, size, type, material, quantity, weight, etc.	Fig. II-16
		DELIVERY DATE CONTROL LIST	This list is used for giving appropriate delivery date, in case that material purchasing department orders articles from outside manufacturers.  All articles are classified to delivery date and order number.	Fig. II-17

MAPS MITSUI ENGINEERING & SHIPBUILDING CO., LTD., CHIBA WORKS

UT. DATE!	PALLE	ET NAME I		7 1 st	F	°2	1	P3 *	PALLE	T TOTAL	TOT	A L		_
6.29	470	NU504 (	2	( 1.7)	24	35.4)	1 5	( 14.0)	31	**************************************				-
1	934	NU526 I	15	(_16.1)_	9	32.2)	1 12	(186.5)	i 36	(236.9)	i			
1		1	-11-	(19.8)	33 (	(67.7)	1 7	(200.6)	1		67 ( 2	88.1)		_
							<u> </u>				1			
7. 2	946	NU523 (	1 11	( 0.0)	1 0 0	( 0.0)	1 5	( 14.8) (104.4)	1 31	(14.6)	i			
	924   934	81G	11-	(_16.8)_ (_5.1)_	i 1 - 1	2.5)	; <sub>2</sub>	(3.4)	-   14-	(11.0)	¦			-
	i	`	22	( 21.9)	l, 13 (	36.7)	1 15	(122.7)	i		50 ( 1	81.3)	i	
					•						!			•
7.3	979	<u>5÷A</u>	0	( <u>0.0)</u>	<u>0</u>	( <u>0.</u> 0)	<u>                                     </u>	(15.6)	<u> </u>	( 15.6)	<u> </u>			_
	 			( 0.0)		( 0.0)	1 1	( 15:6)			1 1 (	15.6)		
7. 4	980	- uusc	30	( 23.5)	<del> </del>	("10.4)	<u> </u> -	7 66.01	42	(120.01				-
	)		30	( 23.5)	5	(19.4)	1 7	( 86.9)	1 72	(127.77	42 ( 1	29.93		
	•		,		•		•			•				-
7.6	970	ROOPO_	<u> </u>	(_0.0)_	<u> </u>	<u>(0 • 0</u> )	<u> </u>	( 5.9)		( 5.9)	<u> </u>			=
	970	80950	0	( 0.0)	1 0	( 0.0)	1 1	( 5.9)	! 1	( 5.9)	!			
			U		U . '				_		2 (	11.01		-
7. 9	980	UU1A	70	(_ <b>9</b> 9•8)	i 31 (	(101.6)	i 1	( 1.9)	102	(203.3)	i -			
1	1 446	Ni:605 ,1	6	( 1.1)	1 0	( 0.ú)	1 0	( 0.0)	1 6	( 1.1)				-
				(0.7)_						( 0.7)				-
	1 446	NB705 1	4	( 0.7) ( 1.4)	1 0	( 0.6)	1 0	( 0.0)		( 0.7)	•			
		N3706		(" 1.6)"	·	( 0.0)	¦ŏ-						 	-
	946	NU527	U	( U.O)	100	(0.0)	1 4	( 26.8)	1 4	( 26.8)	i			
	979	30A4P 1	42	(~47.5)	9. (	("23.5)"	1 0	( 0.0)	71 21	`( <sup>-</sup> 71`.0) <sup></sup>				
			138	(152.9)	40 (	(125:1)	1 5	( 28.7)	_!		183 (3	06.5)		_
7.10	979	UM3PO	5	( 1.9)	1 0	(0.0)	0	( 0.0)	1 5	( 1.9)	, - <b></b>			•
	979	21A		(-8.9)				· · · · ·	_ `	(-16.8)-	·	i		-
		LOSPO_I		( 1+4)_		(_0.0)_				(1.4)_	·	<u> </u>		
		LUOSO 1		( 1.4)	_	0.0)				( 1.4)		<u>!</u>		Ī
	<u>970</u> 970	A05C0 1		( 4.3)		( 0.0) ( 0.0)		( 0.0) ( 0.0)		( 4.3) ( 0.7)		<del></del>		_
	970	NB707		( 1.1)	_	0.0)		( 0.0)		( 1.1)	₽'	i i		
		NB708 1		(-0.7)-		- 0.05-	0	( ~ '0.0) '	4	ζ-ō.i;···		<u> </u>		-
		NU524_1	0_(	(0.0)[	0_(	(0.0)	<u> </u> 5	(_14.8)	15_	( 14.8)	<u> </u>	i		
	934	81H		4:1)			•			( 4.1)				
<del></del>	934	534E		2.1)		7.9)		( 0.0) ( 14.8)		( 2.1)	70 (	<u>, , , , , , , , , , , , , , , , , , , </u>		_
		 	~									771711 44-441		
7.11	979	POKSU-i	39 (	_33•57_i	10 0	37:1)	io-	(-0.0)	-j49 -	(~70.6)		· · · · · ¡		-
الـــــ الـــــــــــــــــــــــــــــ	979	NT581 1	20	_5,0)_[	0_0	. 0.0)	10	( 0.0)	1 28	( 5.0)		i		_
					**************************************	our (BR								
			<del></del>			pipe p						•	AT <u>E 48. 6.22</u> Ion line	-

Fig. II-8 An actual copy of man-hour loading list

	CUT. : DATE : T O T A L	(H)
一	I I I I I I I I I I I I I I I I I I I	1 30 60 40 120 150 180 210 240 270 300
_ _	<u> </u>	. <u> </u>
1	6.291 67 ( 288.1)	)   «««««»««««««««««»»»«««««««««»»»»»»««««««
_	<u> </u>	
*!	7. 11 3 ( 0.0)	
-¦-	_721 <u>_50_(181.31</u> _7311 ( 15.61	11
i		) <u>  • • • • • • • • • • • • • • • • • • </u>
;	7. 51 0 ( 0.0)	
i_	7. 51 2 ( 11.4)	) } • • •
	7. 71 0 ( 0.0)	
<u>*  </u>	_7eto_(o.c)	
ļ	7. 9: 133 ( 30%.5)	<i>,</i>
ļ-	_/,101 /0_(49,4) 	)   **********
•		
		)   • • • • • • • • • • • • • • • • • •
	7.151 0 ( 0.0)	
_1	_7.161_ F2_(_ 42.0)	)
ı	7.17, 130 ( 116.6)	)
- 1	7.161 269 ( 542.5)	自己はたかめのからにはなれたはない。   1
		) *************
. ¦.	7.201 169 ( 186.2)	,
*	7.211 0 ( 0.6 7.221 3 ( 0.0	á i
ij	7.231 202 ( 17:1	)
	7.241 58 ( 45.9)	
ı		
_!.	7.261 234 ( 391.3	
		)   «
	7.291 0 ( 0.0	
•		
÷	1	<u>.+</u> ; 30 60 90 120 150 180 210 240 270 300
i	``	1
		· Man-Hour (liR)
	•	· riant-nour (inv)

Fig. 11-9 All actual copy of a man-hour loading graph for pipe shop

 	L. I MATERIAL L	I. I.GM+ I.DIA	TUO I	l : THICK! ! !	550•	IN/CI	51:01	DRAWING NO	ICUT+	i Isqrap	FAB.	I STA L PRES•	F. I ART []][A.	L.ANG IEN IPRES:	E IDIA.	LBOLT LBOLT LBOLT	   
	I. STPGAS-E	1. 15	21.7	1 2 . 8	1		9660	NUO51 = 32	1 4243	1 247	258		 	1	 	1	ļ
	I .STPG30-L I	l - 15	_ 21.7.	l2 • 8 .  	2 3		953E 966E	1 UU-3A-: 2 1 73C- 6	1.1261 1 4163	1 76	1 25B 1 25B	1 1CK _ 1 10K	l 15 l 15	1 10K	l - 15 l - 15	1 90   1   53	   
,	STPG38-E		21.7	2.8		l	953E	UU-3A- 3   NU05131	i 1693 .l. 2753	i iss	258 258	10K	15	10K	15	-30 10	 
4 .	STPG38=E	1 – 15		2.4.	<u>6</u>	<u> </u>	966E 966E	173C 7. 173C- 16 1 73C- 24	1 656	İ	I2FA I 2SS			1-10K	l 15	   90 .     90	
		1	21.7	  2 • 8_  		 	966E	173C14. 1 73C- 4	.l1240 . 1 3782	1 476	125F	 	   	i	 	10 10	 
6	I SGP≕E	1 15	21.7	1 2.8 1	11	1 1	966E	73C- 13	1 556	I ZAN X	1 2FA		Ŀ	l SK	1 15	90	¦
7	SGP-E	20	27.2	2.3   	12 _ 13_	l	966E.	73C- 21 1 73C- 17	1 475 1_1027	I L ZAN <sup>M</sup>	1 2BA   12SA	] 	l I	l J	l I	0 1	:
3	SGP-E	25	34.0	1 3.2	14	ii	9660	NU051- 25	1 5490	i . 10	2 SF	ί.			i	i o	Í
9	L SCP-E	1 25 1	34.0	1 3.2 1	15	1 1	94.6D	hJ051- 26	1 5490	1 10	1 2SF 1	1	1	1	ì	1 A I	! !
10.	1、ぶしゃービニニ	1 - 25 1	34.0 .1	1 - 3.2 1	16	1 1	97.7.0	hu651- 27	1 5490	1 10	1 2SE	!	t	1	1	ا م آ	 
11	SGP-2	1 - 25 1	34.0	_ 3.2   	17 18	 	966D	NU051- 40	1 1990 1 2402	1 1103	12SF     2BA			 	1	 	 
12	STP338-E	25	34.0	3.4	19	i	4450	NU141- 7	1 5490	1 10	1 2SF			i	 	   0	) J
13	STPG38-E	25	34.0	3.4	20 21	l l	9930 9950	NU141- 4   NU141- 6	1 1697	l I . 13	1 28A I 1 . 25F. i	 	 	l			
14	572333-E	. 25	34.0	3.4	. 22	i i	9450	NU141- 5	1 115	ZAN	25F				 	   0	
	L_ST/:338-& 	l25  	34.0	3.4-	_23.	 	-9950	SEUNO26_   NU031- 40	1-1916		255_J					 	! <del></del>
16   l	STPG38=2   	25      	34.0	3.4	25 - 26 - 27	 	9950 I 966E I 9950 I	SEBNO- 27 . 444- 10 NU141- 3	1 995 1 1831 1 2643	li	25F     ., 2BA     25B				1 3	l o i	
17 I	STPG38-E I	25 1	34.0 !	3.4	23 (	1	966E 1	73C- 8 SELNO- 26	1 1550 1 1643	l 2307 l	25F     _ 2BA			ا اعداد ا	1 1	1 0 1	
16_  	_STPT38-E.	25	j. 0446	3.4 j	ا 0د ا 31		966E 1	22ME- 9 22ME- 7	1 . 643	ZAN*	28A     28A						

Fig. 11-10 An actual copy of pipe cutting plan

* CUT DAT	B 22-9-1976 **	,	. ! !			MATERIA (P	L LIS					<u> </u>		PAGE
** STEEL P	IPE (40-150) *	*							!	: 1 . ' .	<u> </u>		<u> </u>	
SYSTEM	SHIP NO.	A	COUNT NO.	MATERIAL: 1	NOM. DIA.	SCHEDULE	Q'TY	ARTICLE CODE	LENGTH	WEIGHT	DELIVERY DATE	DWG.NO.	ORD	ER NO
AD	CS1095E	P.L	_1605_	STPG38-E	<u> </u>	40	1	140554_	5.5	22,55				<del></del>
. SC I	CS1095D	l i Ipi	1606-1	STPG38-E	40.		l I, <b>2.</b> .i	l140554	11.0 .					
. 1F i	CS1095E .	l I IPI	0813. I	STPG38-E: I	40	i 40 i i	<b>1</b> :	l . l . 140554	5.5.	22.53	<b>.</b>		<b>:</b>	
2L1	CS1044E	l   l P.l	_0805_	  _STPG38=E	40	40	  1:			l  22.53	<u> </u>			
4D	i	1 1	ı	STPG38-E: I	40	40	. 2:	140554	11.0	45.07			!!!	
4W	' :	1 1	. 1	STPG38-E	40	; 40 :	3	140554	1 16.5.	1 67.60	1 !!		j ! :	
	,	1 1		STPG38πELI	40	AO !		140556_	22.0	1 120.37	4 1			' '
. AV	+	1 1	- 1	l			1	li i	1   1   1	1	1	1 1		
	CS1095E	1 1		1	501	40-	1	1140558	_   5.5  . 	29.94	1		-	
BL !		1 1	1	STPG38-E: I	50	40-	-!. <b>3</b>	1140558.	16.5 	89.82				
CA		1 1	1	SIPG38-ELI	50'	40	<del></del>	140558 	44.0 	1 239.53	-		<del>                                     </del>	<del>                                     </del>
.SC !	CS1095D	l I	.1606 l	STPG38-E!  	50	40	: <b>2</b> ;   	l140558. l	!	1.¦, 59.88 1	<u> </u>	[		-
1F !	CS1095E	IPI I I	0813.	STPG38-E:   	: _; . 50 <u>;</u>	40	<b> 1.</b>   	l140558 l .	.  5.5. 	l 29.94 l	1 :		- -	- -
4Fl	CS1094E	l P.I	08011	_STPG38-E'	<u> </u>	Ao	1-1-	<del> 1</del> 40558	<del> </del> 5.5	<del>1 2</del> 9.94	ļ	<u> </u>	<del>                                     </del>	
5L i	CS1094E	P	0805.	STPG38-E!	50:	40	.! <b>3</b> .	140558	1 116.5 .	89.82	İ			
AD i	.CS1094E	įρį	1605	STPG38-E:	50!	80		140560	5.5.	41.03		j ,		
2L	CS1044E	P	-0805-	_STPG38-E:	<u>'</u> 50	80		140560_	j5.5	41.03	<u> </u>		•	
BL	. CS1095D	P	1602.	STPG38-EI	65!	- 40··	2;	.:.140562	., .11.0	100.30				! !
SD	CS1095D	P	1607	STPG38-E:	65	140.	1	140562.	5.5.	50.15				
WD	CS1095D	P	_1601_	_STPG38=E:_	65 <u> </u>			140562		50-15	<u> </u>	<u> </u>		$\coprod$
<b>1</b> 5 .	.CS1044E	l I	0802.	STPG38-E. I	65.	40 .	1,	140562.	5.5.	50.15				.
7H .	CS1094E	l l IPl	0806	   STPG38 <b>-</b> E!		40 .	l : 2,	  140562		1 -100.30				
co!	CS1044E	  P_!	1901   1901	  _STRG38=EL	80 <u></u>	·AO		  140566_	l · l5-5			l i ' I		
EP.	l	1 1	0602.	STPG38-E: I		. :40 .	i i 1.1:	l I .140566	1 : : 5.5.	62.37	1. ; ;		<u> </u>	
		l İ	i	i i		' :	1	t	1 ' :	1	1 !	1 , ;	1	

Fig. II-11 Copy of material list (Pipes)

CUT DATE 22-9-1976 **	+	(FLAN	GE)		•				PAGE
SYSTEM ( SHIP NO. ( )	MATERIAL	1 NOM. DIA. I	l Q'TY	ARTICLE CODE	Q'TY		DELIVERY DATE	I DWG.NO.	• • • • • • • • • • • • • • • • • • •
5K SLIPI CS1080E IPI		15:	-	582103 '			DATE		ORDER NO.
5K SLIPI CS1094D IPI	5541	15	-j''	582103		2.40	1		
5K SLIPI CS1037D IPI	SS41 · ·	20	1 12	   582104	i i 12	4.44	1 ' '		
SK SLIPI CS1044E IPI	5541.	20	1 7	1   582104	7	1 2.59	! ; ; ; ; ; ; ; ; ; ; ; ; ; ; ; ; ; ; ;		
5K SLIPI CS1080E IPI	I \$\$41. : ·	20	-j — —   17	582104	1 17	6.29	1		
SK SLIPI CS1095E IPI	   SS41	20	6	582104	6	2.22	l' ; ;		
5K SLIPI CS1037D IPI	5541.	25	1 1	582105	1	0.45	1		
5K SLIPI CS1037F IPI	1 5541	25	-	582105		3.60	1	<del></del>	
SK SLIPI CS1044E IPI	1 5541	11 25 1	1 12.	- 582105	12	5.40	l; ~;;		
5K SLIPI CS1080E IPI	I SS41	1 25 1	j	582105	, ,	1 1.35	l		
SK SLIPI CS1094D IPI	SS41:	25.	-i I 1.	. 582105	1 1	0.45	I <del></del> -		
5K SLIPI CS1037D IPI	1 5541   '	40	i i 12.	582108	12	9.96	1 ; ; ;	! ; ;	
5K SLIPI CS1037F IPI	5541	40	1 5	582108		i;	1		
5K SLIPI CS1044D IPI	1 5541	40!	i — —	582108		3.32		j- <del></del>	
5K SLIPI CS1044E IPI	i   5541	40	73	582108	73	60.59	) · · · · ·	. ;	-i-
JK SLIPI CS1080E IPI		40	( · )	Į į	· '	1	`` '		'   '
JK SLIPI CS1094D IPI	SS41.	·	- -30_	582108_	30	24.90	I		ļ <del></del>
JK SLIPI CS1095E IPI	5541   SS41	40	17	582108	17	14.11	<b>]</b>	٠ !	
JK SLIPI CS1037D IPI	SS41	40	9	582108	. 5 	4.15	l' i i	,	
5K SLIPI CS1044E IPI	SS41	50	24	582109	24	25.68		<u>-</u> -	:
5K SLIPI CS1080E IPI	" I	50	35	582109	35	37.45			· ;; ·
5K SLIPI CS1094D IPI	1 5541	50	1 17	582109	17	18,19	1	<del></del> .	· · · ·
	5541	50	2_	582109	2	2.14	<del></del> (	<del></del>	
SK SLIPI CS1095E IPI	5541 	1 50	1 15	582109	15	16.05			;

Fig. II-12 Copy of material list (flange)

Fig. 11-13 Sample of NC cards

1247 CS1100-TDB4S-10 50 P-3SF STPG38-E(# 80) CK 12. 7 CS1100 105S- 25 50 P-3SF STPG38-EC# 80) CK

Fig. 11-14 Identification Number Label




Fig. 11-15 Numerical pipe piece list




Fig. 11-16 Copies of actual palletting table


	JOB NO. CSO			DELIVERY					ÄTE 24TH ÖCT.				<del></del>
<u>*2</u>	*3 X4 ×5	471209	1471225	1480110	1480131	1480210	1460220	1480312	1480420	1480507	 	I	
BV .	5 150 FC25	753905		. 1	1753905	1	1	!	!	1	1	!	!
в	5 175 FC25	753905	•			753905			i · · ·	i	i	i -	i -
BV	5 200 FC25			753905	Ī	1	1753905		_ <u></u> !	1	<u>;</u>		!
BV	5 250 FC25			753905	į	<b>i</b> "						•••	ľ
в	5 300 FC25	753905	i	753905	į	i	•		i · ·	i	i		!
в٧	5 350 FC25		!	1753905		1753905	753905		!	1	!	·	!
BV	5 400 FC25		i	1753905			• •	·· ~ <del></del> ·	. !	į			
BV	5 600 FC25	753905		. i			••			-			!
BV	5 700	!	į	1754390		-			1/24390	I	!	1	1
					ļ ·				754882		ļ	i	· · · -
`BV	10 100 FC20	753905				1		******	-	-1	!		1
BV	10 100 SC49	l	753639	I	į -	ţ			ı	1	ı	1	1
BV	10 125 FC20	 1		1	1 1753905					ļ	¦	ļ	. 1
BV	10 125 SC49		1753639		4	1	• •	•	1	1	1	<u> </u>	1
BV	10 150 FC25	753905	-	-	_				ı	ı	1	i	Ī
в	10 150 SC49	 	.1 1753639	1	. 1					.1	ı J	i	ļ
	 10 200 SC49	1	1 1753639	.	. 1       . 1				1	j i	1	İ	İ
	10 400 SC49	l	1753639	-1				-			•		<u>.                                    </u>
	10 600 SC49	l	-	1	.1	ļ	·		-		İ	į <u>.</u>	i
	5 65 SC49	I .	1.	į	.	· i	-			i	1	<u> </u>	ز
	5 80 SC49	•	<u>:</u> -	<u>-</u>	_: 	<u>:</u> 1	<u>.</u>	<u> </u>	1 10110	1		WERY DATE	nė i lit
	5 100 SC49	I.,	ļ		1753906	1 _	į		,—— ·	ļ	- 1	VERY DATE 1209 SHOWS 1-DAY	"9TH_OEC
	20 4	!	i.	: 1	1	1	i	- [	<u> </u>	1753796	· <del>[</del> -}[	MONTH YEAR	
FCX		753909	- <u> </u>	753909	<u> </u>		<del>- j</del>	<del>-</del>			.i	MBOL	<del></del> -
FCX	5 65 FC20	<b>i</b>	. į <b>.</b>	.	-i - · · · ·	į	755611	. į		į	.i\	essure	
	10 20 BC	i	i	.	. <b>j</b>	. <b>.</b>	į  –	· <b>i</b>		.i	.i	MINAL DIAME	TER
1 26/1	-0 20 00		. j		į	j			1783906	ļ	X5:M	VERIAL	<del></del>
FCX	10 20 BC6		i	į	į		. [	<u>i</u> -	1	į .	<b>i</b> .	<u>.</u> .	!
rtx	TO 50 BC9	ì	1	1	ł	1	1	1	783906	1	}	I	1

Fig. II-17 Delivery date control list


# G. Computer Configuration to Accomplish the Software

Shown below is one example in case of Mitsui Cbiba Works The machine can be replaced by the one having equivalent capacity.

#### MINI-COMPUTER WITH GRAPHIC DISPLAY FOR GPS



Core size ; 64K Byte One work ; 16 Bits Addition ;  $0.8 \sim 1.8 \mu S$  Floating point multiply ;  $16.8 \sim 28.6 \mu S$ 



User's program area in main memory; 384KB
Card reader/puncher; 1 set
Line printer; 1 set
Magnetic disk equipment; 1 spindle
Magnetic tape equipment; 2 devices


Fig. 11-18 Computer configuration to accomplish the software package

**Section IV** 


### **Section IV**

Advanced Research and Development INDEX

- A. General
- B. Van-Stone Couplings
- C. Cypress Welding Research and Development
- D. ESAB Industrial Robot Welding Research and Development
- E. T/Drill Branch Collaring 90 Degree Research and Development
- F. Machine Cutting Branches



T/Drill pipe collaring for 90 degree pipe branches.



Semi-automatic plasma welding process.

#### A. General

During our research effort, some advanced processing equipment has been identified.

1. Van-Stone Couplings versus Weld Joints

- Cypress Engineering Company Orbiting Pipe Saddle Welding
- 3. ESAB Company "Robot" Welding 4. T/Drill 90 Degree Branch Collaring

These four items relate to the sub-assembly area of the automated pipe facility. This is the area where application of individual automatic equipment is the most challenging.

#### B. Van-Stone Couplings Versus Weld Joints

Cost effectiveness of subject couplings has been demonstrated. It is a regulatory body approved alternate to weld joints. Research is proceeding for production application of subject couplings.

C. Cypress Engineering Company Orbiting Saddle Welding This machine is in the developmental stage. It has been established that the subject tooling can follow the complex contours set forth by pipe saddle joints. The Cypress Engineering Company equipment has been extensively modified as evaluation of equipment has progressed. Presently, this unit has a mechanical linkage capable of optimum varying torch angles for any place in its 360 degree orbit. Additionally, it can simultaneously oscillate to produce a weld weave pattern. The oscillation is a fixed equal dwell. Since most of the saddle joint is essentially a horizontal position weld, a variable dwell oscillation pattern should be pursued. Test welds made to date indicate feasibility.

This welding process is approved for nuclear construction with saddle in joints. Further development is required for application with P-1 ship systems. This process has proved very economical for processing piping with diameters of 30 inches and above.

D. ESAB Company "Robot" Welding

1. Welding Fair-Essen, Germany-1977

It was observed by our technical people that use of industrial-' 'robots" for welding is accelerating at a rapid pace in Europe. Basically, "robots" are divided into two categories.

a. Manually Programmed-e.g. Hobart-Tralfa b. X-Y-Z Axis Programmed-e.g. ESAB-ASEA Contact with technical people in Europe indicates category b. better conforms to accuracy requirements for

welding.

2. "Robot" Welding of Pipe Saddles
Since September, 1977, research has progressed
with the "robot" equipment. The "robot' is a more
expensive alternate to the Cypress equipment with
a wider field of application. It should be noted that
this equipment can be utilized for high production
rate and repetitive assembly work such as (a) Pipe
Hangers; (b) Small Foundations; and (c) Brackets,
as well as Pipe Branch Weldments. There are
numerous repetitive assemblies in ships. Historically, this work is accomplished in fabrication
or sheet metal shops. This work could be redirected
to the automated pipe assembly area.

#### E. T/Drill 90 Degree Branch Collaring

This equipment makes "pull outs" on pipe and eliminates the need for purchased T-fittings. Avondale Shipyards has purchased two of these units.

Cost analyses indicate the use of "pull outs" can save as much as 98 percent of the material cost (conventional joints) per ship set on a series of Navy vessels currently under construction at Avondale.

Further research with this equipment will involve studying welding systems for the development of procedures on such materials as carbon steel, copper-nickel and 300 Series stainless steel, utilizing the T/Drill collar for joint preparation.

Research will continue to determine the feasibility of automating the welding of T-Drill weld joints.

#### F. Machine Cutting Branches

During the research efforts on 90 degree fitting and welding of branches, the hole in the main body pipe and the shape of the branch has been accomplished by burning. In order to improve this weld joint, it is recommended that additional research efforts be directed toward the feasibility of machine cutting the hole as well as the contoured end of the branch pipe.



Welding robot A30 A



# Mechanized welding - from a technical point of view

When mechanizing or automating a welding process it is often necessary, as in practically all mechanization, to adapt the workpiece to the automatic process in question. In the case of arc welding, this is a requirement of particular importance since in itself, arc welding is a relatively complicated process which normally requires an intimate interaction between man, machine and workpiece. Long series were previously called for if profitability was to be reached. This meant that short series, varying series, and components in which the joints lacked sufficient accuracy, continuity or regularity were seldom suitable for profitable mechanization with the techniques available.

Under ideal conditions, where the above requirements are fulfilled a


product-adapted machine is often the best and most profitable solution. For example, a number of arcs can be operated simultaneously or in sequence which in most cases, understandably, makes for high production rates. In general, this type of facility or mechanical welding equipment is used for peripheral or continuous straight welds; this applies to large as well as small production facilities.

Robot arc welding Thanks to the development of semiautomatic welders in the late 1950's, gas metal-arc welding made its break-through in industry and today, semi-automatic gas metal-arc welding is widespread in the industrialized


is widespread in the industrialized world. For many years, there has been a definite need of a more advanced, mechanized arc welding machine for the type of workpiece which does not satisfy the requirements on series length, joint position and regularity.

This is probably most evident in the case of small and medium-size components.

Almost in every welding shop, much can be gained from improvements in the work environment. To achieve such improvements and simultaneously to eliminate tiresome and monotonous jobs within the welding industry has been one of the principal aims of ESAB'S development group for a considerable time. Through significant advancements in the field of robot technology, it is now possible to carry out gas metal-arc welding as well as resistance welding/spot welding with industrial robots to a sufficiently high level of accuracy for a substantial part of the industry's welded products. In this field, the ESAB A30 A Welding Robot is a leading contender.










ESAB here presents the ASEA welding robot, especially designed for arc welding. The most significant advantages of this system can be summarized as follows:

- Improvement in work environment due to elimination of tiresome and monotonous jobs and the extraction of welding fumes.
- Significantly increased production.
- High, consistent welding quality.
- Versatile equipment, suitable for a great variety of workpieces.
- Short operation time, which reduces processing time.
- Low capital expenditure requirement compared with type restricted welding equipment.
- Easily operated and programmed.
- Generally adaptable to existing designs.

When to use robot welding As previously mentioned, type-restricted, mechanized or automated welding equipment should be used for products which are to be manufactured in long series and where the geometry of the joints is uncomplicated. In some cases, type-restricted equipment can be modified to be used for a number of different workplaces or for different versions of the same workpiece. Furthermore, the welding of uncomplicated circular and linear joints can often be automated by using standard circumferential welding positioners or automatic column and booms. In order to attain good results, the following applies to both type-restricted equipment as well as welding robots.


- Material possessing good weldability. must be used.
- The material must be free from paint, impurities, grease, oil, scale etc.
- The joints must be well prepared and offer good fit.
- The workpieces must be uniform or the positioning of the joints be relative to each other or correspond to a reference point (datum plane, hole or edge). Permissible deviations vary from case to case, but generally speaking, the lighter the materials to be welded, the tighter the tolerance required. The type of joint is also of importance, as are the requirements made on penetration, weld appearance, strength etc.







# ADVANCE PIPE AND SHEET BRANCHING METHOD


Formed collars from 5" to 20" in 20 minutes per collar. Increased flow properties, joint quality and joint strength! Decreased material costs, labor cost and joint inspection cost.








Hole saw and conical cutter form elliptical pilot hole



STEP 2/

Machine grinding of edge to finish collar



STEP 3/

Machine forms collar utilizing formation pins

STEP 4

Machine mills edge to finish collar

### **TYPE 500:**

Eliminates-T-joints and flanges

Eliminates-Extra welds and x-rays

Eliminates-Labor and materials for

miter joints

Eliminates-Stocking of joint pieces

Eliminates-Weaknesses at branching points

## **SPECIFICATIONS**

Capacity: Collar diameters-5" to 20"

Max. main pipe O. D.-4O"

Max. wall thickness-1/4" stainless steel

-5/16" soft steel

Height: 106" Width: 51" Depth: 63" Weight: 5000 lbs.

Connections: 220/440 V 30 ph 60 Hz

12 hp.

Air-100 P.S.I.

T/DRILL,

727 W. ELLSWORTH, BLDG.8/ ANN ARBOR, MICH.48104 TELEPHONE 313-995-2187



Supercedes Prevailing Pipe Branching Methods

Putting a branch on a pipe is a problem.

A pipe branch is expensive to make if you use a separate T-part. You have to pay for the part itself and for linking it up to the main pipe and checking the connections. And if you cannot utilize a branch part the traditional methods are uneconomical on account of their slowness and because of machine expences.

#### Type 150 provides a short-cut

A T-Joint Drill Type 150 can work the hole and the collar straight onto a pipe in 5-15 minutes.

Owing to the collar the pipe branch will not impede the flow.

And there is no separate branch part. Costs are saved on pipe parts and on work and x-ray checks of the two connections joining the T-part to the main pipe.

Pipe materials
Copper
Aluminum, brass
Copper, nickel
Stainless steel
Steel

Operating range of collaring heads

#### branch pipe diameter

168	Collaring Head No. 5 Main pipe wall thickness S=3 (4) '
120	Collaring Head No. 4  Main pipe wall thickness S=3 (4) I ness is workable
90 76	Collaring Head No. 3 When Main pipe wall thickness S=3   Collar dia- meter is
46	Collaring Head No. 2 not larger than 0,85 of the
	main pipe Main pipe wall thickness S=2 diameter
	10 10 70 00 100 100 100

42 48 76 90 120 168-400 main pipe diameter

#### **Approvals**


The Technical Research Centre of Finland has tested and the Technical Inspectorate has given a resolution (1865/210/76) of the use of Larikka T-Joint Drill Method in the manufacture of collared branches.

On the basis of the above Det Norske Veritas has given a restrictive approval (October 14, 1976) for the use of the method.


#### Manufacturer:




LARIKKAOY 01630 Vantaa 63 Finland Telephone: 90-847 077 Cables: Latool




Machine drills elliptical pilot hole.



Edges of ellipse are filed with a machine file.



Machine draws on collar with aid of the formation pins of the collaring head. The adjustment of the head is continuous. The effect of the pipe wall thickness is compensated by a fine adjustment system.



Machine then works the collar edge for abutment joint.

# **Section V**

# **Section V**

Equipment Suppliers INDEX

- A. General
- B. Pipe Shop Equipment Suppliers
- C. Hardware Systems Suppliers
- D. Software Package Suppliers

#### A.General

This section is designed to provide the reader with a list of companies that supply automatic or semi-automatic equipment. It must be noted that there are numerous companies in the world that manufacture this type of equipment. However, only a few major suppliers are mentioned in this section.

The equipment listed under the heading of Pipe Shop Equipment Suppliers can be acquisitioned individually. The machines are automatic or semi-automatic, and can be integrated into a production system with modifications.

There are five companies that can provide a semi-automatic or automatic pipe fabrication facility. These systems, however, are limited as to pipe size and alloy mix. These companies are listed under the heading of Semi-Automatic or Automatic Pipe Fabrication Systems Suppliers.

A software package is essential to the efficient operation of a semi-automatic or automatic pipe fabrication facility. Five suppliers are listed. It must be noted that in the near future a software package of United States' origin will be available, which will provide the pipe detailing function.

This system is being developed by Newport News Ship-building and Dry Dock Company, under contract with the Maritime Administration.

B. Pipe Shop Equipment Suppliers

1. Racking Systems, Semi-Automatic

Ishikawajima-Harima Heavy Industries Company, Ltd. (IHI)

Mitsui Engineering& Shipbuilding Company, Ltd. Oxytechnik

Steffan Manufacturing Company Systems Equipment Company

Surface Preparation and Coating, Semi-Automatic Binks Manufacturing Company

Ishikawajima-Harima Heavy Industries Co., Ltd.

Mitsui Engineering& Shipbuilding Company, Ltd. Oxytechnik

Vacu-Blast Corporation Wheelabrator-Frye, Inc.

3. Cutting and Measuring, Semi-Automatic Cypress Welding Manufacturing Company Do-All Company

Fairileld Machine Company, Ltd.

Ishikawajima-Harima Heavy Industries Co.,

Mitsui Engineering& Shipbuilding Co., Ltd. Oxytechnik

W. K. Stamets Company

Steffan Manufacturing Corporation

Vernon Tool Company

Wallace Supplies Manufacturing Company

4. Marking Devices, Semi-Automatic

Ishikawajima-Harima Heavy Industries Co.,

Mitsui Engineering& Shipbuilding Co., Ltd. Oxytechnik

W. K. Stamets Company

Wallace Supplies Manufacturing Company

5. Conveyer Systems and Kickouts Do-AU Company

Ishikawajima-Harima Heavy Industries Co.,

Mitsui Engineering& Shipbuilding Co., Ltd. Oxvtechnik

Pandjiris Weldment Company

W. K. Stamets Company Vernon Tool Company

Wallace Supplies Manufacturing Company

Contour Cutting

Cypress Welding Manufacturing Company Ishikawajima-Harima Heavy Industries Co.,

Mitsui Engineering& Shipbuilding Co., Ltd.

W. K. Stamets Company

Steffan Manufacturing Company

Vernon Tool Company

7. End Preparation

Conrac Corporation

Fairfield Machine Company, Inc.

Ishikawajima-Harima Heavy Industries Co.,

Mitsui Engineering& Shipbuilding Co., Ltd. W. K. Stamets Company

Steffan Manufacturing Corporation

Vernon Tool Company

8. Hole Burning Devices

Cypress Welding Manufacturing Company Ishikawajima-Harima Heavy Industries Co.,

Koikie Sanso Kogyo Co., Ltd. Steffan Manufacturing Corporation

9. Branch Welding

Research and Development

10. Flange Welding and Finishing, Automatic ESAB-HEBE Company Ishikawajima-Harima Heavy Industries Co.,

Mitsui Engineering& Shipbuilding Co., Ltd. Oxytechnik

11. Bending with/without Flanges, Automatic Comae Corporation Ishikawajima-Harima Heavy Industries Co.,

Mitsui Engineering& Shipbuilding Co., Ltd.

12. X-ray, Semi-Automatic Research and Development

#### SEMI-AUTOMATIC OR AUTOMATIC PIPE FABRI-**CATION SYSTEMS SUPPLIERS**

C. Hardware Systems Suppliers

Ishikawajima-Harima Heavy Industries Co., Ltd.

MECAVAL International/USA

Mitsui Engineering& Shipbuilding Co., Ltd. Oxytechnik

D. Software Package Suppliers

Hitachi Shipbuilding Co., Ltd.

Ishikawajima-Harima Heavy Industries Co.. Ltd.

**Kockums** 

Mitsui Engineering & Shipbuilding Co..,Ltd. Newport News Shipbuilding & Dry Dock Company (Under Development)

Hardware can be provided, and in some cases the software, to perform as an integrated system to produce the following functions:

Automatic Pipe Storage
Automatic Pipe Cutting
Automatic Measuring
Automatic Contour Cutting
Automatic Fitting/Welding Straight Pipe Pieces
Automatic Flange Fitting & Welding
Automatic Flange Cleaning
Automatic Flange Cleaning
Automatic Bending with/without Flanges
Automatic Transfer Device Kickouts
Automatic External Surface Preparation and External
Coating

Coating

Acknowledgements

## Acknowledgements

Many people have made significant contributions to the development of the feasibility study of semi-automatic pipe handling system and fabrication facility. While it is impossible to list every person who has made a contribution to the project, an attempt is made to mention those who were most directly involved in its development.

The following were responsible for the administration and supervision of the project

- O. H. Gatlin-Vice President, Corporate Plant Engineering and Maintenance Avondale Shipyards, Incorporated Program Manager
- R. A. Price-Industrial Engineer Avondale Shipyards, Incorporated Project Administrator
- A. S. Lasseigne-Mechanical Engineer Avondale Shipyards, Incorporated Project Engineer

The advisory committee was comprised of the following personnel:

- A. L. Bossier-President Avondale Shipyards, Incorporated
- E. Blanchard-Vice President, Production Operations Avondale Shipyards, Incorporated
- D. L. Clark-Vice President, Production Mechanical Trades Avondale Shipyards, Incorporated
- T. Doussan-Vice President and Chief Engineer Avondale Shipyards, Incorporated
- W. Alexander- superintendent, Welding Department Avondale Shipyards, Incorporated
- R. J. Duhon-superintendent, Pipe Shop Avondale Shipyards, Incorporated
- A. Ebright-Director, Quality Control Test Department Avondale Shipyards, Incorporated
- O. K. Tilley-Supervisor, Mechanical Development Section Avondale Shipyards, Incorporated

Special acknowledgement goes to the many domestic and foreign company representatives who provided the research team with excellent on site tours and technical data.

## **Special Acknowledgements**

Airco Welding Products

Astilleros y Callers del Noroeste, S.A.

Babcox/Wilcox, Incorporated Bath Iron Works Corporation

Bayer A.G.

Bethlehem Steel Corporation Binks Manufacturing Company

Chantiers De L'Atlantic Conrac Corporation

Cypress Welding Equipment, Inc.

Dimetrics Company E. I. Dupont, Inc.

ESAB-HEBE Company Fairfield Machine Company

Mr. Frank Fradella (Avondale Shipyards, Incorporated)

Gaido-Lingle Company, Inc. General Dynamics Corporation M. T. Gilliland Company

Mr. S. A. Grubish (Consultant Engineer) Hitachi Shipbuilding Company, Ltd.

Howaldtswerke-Deutsche Werft (H.D.W.)

**ITT Research Institute** 

IngalIs Shipbuilding, Division of Litton Industries Ishikawajima-Harima Heavy Industries Company, Ltd.

(IHI) Italcantiere Kockums

Leetonia Pipe & Supply Company

Lincoln Electric Company

Lucas Machine

Mr. Phillip T. MacAbee

(Avondale Shipyards, Incorporated)

Magnatech Co.

MECAVAL International/USA

Messer Greishiem Co.

Mr. Leonard Milacek

(Avondale Shipyards, Incorporated)

Miller Electric Co.

Mitsui Engineering& Shipbuilding Co., Ltd.

Mitsui Engineering& Shipbuilding Co., Ltd., Chiba

National Shipbuilding Research Program National Steel and Shipbuilding Company

Newport News Shipbuilding and Dry Dock Company

Orvath Precision Model Company

Oxytechnik

Pangbom Corporation Rauma Repola Shipyard

Mr. Roy Roux

(Avondale Shipyards, Incorporated) Benjamin F. Shaw Co.

Mr. K. Shiozawa (Mitsui)

Southwest Fabricating & Welding Co., Inc.

W. K. Stamets Company

Steffan Manufacturing Corporation Systems Equipment Company

T-Drill, Incorporated Teledyne Pines Company Texas Pipe Bending Co. Todd Shipyards Corporation

United States Navy, Supervisor of Shipbuilding

Vacu-Blast Corporation Vernon Tool Company

Wallace Supplies Manufacturing Company

Wartsila Shipyards MELCA Lastechniek Wheelabrator-Frye, Inc. Mr. G. Wilkens (Oxytechnik)

Tangerich